


INTERCONNECT SCHEDULE OF QUANTITIES

QUANTITY	UNIT	ITEM DESCRIPTION
2,369	FOOT	UNDERGROUND CONDUIT, GALVANIZED STEEL, 2" DIA.
5	EACH	HANDHOLE
2	EACH	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION
4,077	FOOT	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C
4	EACH	DRILL EXISTING HANDHOLE
59	FOOT	DETECTOR LOOP REPLACEMENT
7,879	FOOT	REMOVE ELECTRIC CABLE FROM CONDUIT
3	EACH	REMOVE EXISTING HANDHOLE
1	L SUM	TEMPORARY WIRELESS INTERCONNECT, COMPLETE
4,100	FOOT	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, MM24F SM12F
1	EACH	RE-OPTIMIZE TRAFFIC SIGNAL SYSTEM LEVEL 1



TEMPORARY WIRELESS INTERCONNECT SCHEMATIC

NOTE:
THE TRAFFIC SIGNAL CONTROLLER EQUIPMENT FOR THIS PROJECT SHALL BE "EAGLE" TO MATCH THE EXISTING ADJACENT SYSTEM.

Plotfile: 2/1/2013 10:41:18 AM BY: JSCM/dfr

Engineering Enterprises, Inc.
CONSULTING ENGINEERS
52 Wheeler Road
Sugar Grove, Illinois 60554
630.466.6700 / www.eetweb.com

KANE COUNTY DIVISION OF TRANSPORTATION
41W011 BURLINGTON ROAD
ST. CHARLES, IL 60175

DESIGNED	J.V.W. SWM
DRAWN	J.P.S.
CHECKED	J.R.L.
DATE	12/7/12

REVISED	J.P.S. 02/04/13
REVISED	-
REVISED	-
REVISED	-

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

FABYAN PARKWAY TEMPORARY WIRELESS INTERCONNECT AND INTERCONNECT SCHEMATIC

SCALE: N.T.S. SHEET NO. 3 OF 4 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
363	10-00404-00-CH	KANE	59	33
C-91-496-10		CONTRACT NO. 63818		
ILLINOIS FED. AID PROJECT CMM-9003627				

COPYRIGHT 2012 ENGINEERING ENTERPRISES, INC.

Path: \\S:\projects\63818\Fabyan\Drawings\63818-Fabyan.dgn