

SUMMARY OF QUANTITIES				0005 ROADWAY 70% STP 30% LA	0005 ROADWAY 100% LA
CODE NO	PAY ITEM	UNIT	QUANTITY		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	59	59	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	154	154	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	5	5	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	5	5	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	5	5	
25200110	SODDING, SALT TOLERANT	SQ YD	154	154	
25200200	SUPPLEMENTAL WATERING	UNIT	5	5	
28000510	INLET FILTERS	EACH	16	16	
30300001	AGGREGATE SUBGRADE IMPROVEMENT	CU YD	41	41	
31101200	SUBBASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	516	516	
35800100	PREPARATION OF BASE	SQ YD	12,070	12,070	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2,414	2,414	
40600300	AGGREGATE (PRIME COAT)	TON	49	49	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	25	25	
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	664	664	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	118	118	
40600990	TEMPORARY RAMP	SQ YD	244	244	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1,352	1,352	
42001300	PROTECTIVE COAT	SQ YD	3,412	3,412	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	31	31	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	53	53	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	3,951	3,951	
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	267	267	
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	420	420	
42400800	DETECTABLE WARNINGS	SQ FT	333	333	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	115	115	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	460	460	
44000600	SIDEWALK REMOVAL	SQ FT	4,638	4,638	
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	151	151	
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	151	151	
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	151	151	
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	151	151	
60266600	VALVE BOXES TO BE ADJUSTED	EACH	4	4	
60406100	FRAMES AND LIDS, TYPE I, CLOSED LID	EACH	5	5	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6,12	FOOT	260	260	
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6,24	FOOT	200	200	
67100100	MOBILIZATION	L SUM	1	1	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	1,917	1,917	
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	924	924	
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	10,130	10,130	
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3,426	3,426	
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	422	422	
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	816	816	
70300510	PAVEMENT MARKING TAPE, TYPE III - LETTERS AND SYMBOLS	SQ FT	219	219	

SUMMARY OF QUANTITIES				0005 ROADWAY 70% STP 30% LA	0005 ROADWAY 100% LA
CODE NO	PAY ITEM	UNIT	QUANTITY		
70300520	PAVEMENT MARKING TAPE, TYPE III 4"	FOOT	3,049	3,049	
70300540	PAVEMENT MARKING TAPE, TYPE III 6"	FOOT	1,204	1,204	
70300570	PAVEMENT MARKING TAPE, TYPE III 24"	FOOT	122	122	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1,015	1,015	
78005100	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	462	462	
78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	5,065	5,065	
78005130	EPOXY PAVEMENT MARKING - LINE 6"	FOOT	1,713	1,713	
78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	211	211	
78005180	EPOXY PAVEMENT MARKING - LINE 24"	FOOT	408	408	
81028350	UNDERGROUND CONDUIT, PVC, 2" DIA.	FOOT	159		159
88600600	DETECTOR LOOP REPLACEMENT	FOOT	698	698	
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	2	2	
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	2	2	
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	11,952	11,952	
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	26	26	
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
<del>70101600</del>	CHANGEABLE MESSAGE SIGN	CAL mo	4	4	
X7830068	GROOVING FOR RECESSED PAVEMENT MARKING, LETTERS, NUMBERS AND SYMBOLS	SQ FT	462		462
X7830070	GROOVING FOR RECESSED PAVEMENT MARKING 5"	FOOT	5,065		5,065
X7830074	GROOVING FOR RECESSED PAVEMENT MARKING 7"	FOOT	1,713		1,713
X7830078	GROOVING FOR RECESSED PAVEMENT MARKING 13"	FOOT	211		211
X7830090	GROOVING FOR RECESSED PAVEMENT MARKING 25"	FOOT	408		408
X8140215	HEAVY-DUTY HANDHOLE TO BE ADJUSTED	EACH	2		2
XX090445	SAWCUT AND SEAL NEW JOINTS	FOOT	3,414		3,414
Z0004522	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 6"	SQ YD	12	12	
Z0004530	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 8"	SQ YD	19	19	
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	8	8	
Z0023202	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	16	16	
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	164	164	
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	

\* SPECIALTY ITEM