



NOTES:

1. USE BLACK LETTERING ON ORANGE BACKGROUND.
2. ERECT SIGNS IN ADVANCE OF THE LOCATION FOR THE "ROAD CONSTRUCTION AHEAD" SIGN AT LOCATIONS AS DIRECTED BY THE ENGINEER.
3. ERECT SIGN ① WITH INSTALLED PANEL ② ONE WEEK PRIOR TO THE START OF CONSTRUCTION.
4. REMOVE PANEL ② SOON AFTER THE START OF CONSTRUCTION.
5. SEE SPECIAL PROVISION FOR "TEMPORARY INFORMATION SIGNING" FOR ADDITIONAL INFORMATION.
6. ONE SIGN ASSEMBLY EQUALS 25.70 SQ. FT. (2.3 SQ. M.)
7. SHALL BE PAID FOR AS TEMPORARY INFORMATION SIGNING.

ALL DIMENSIONS ARE IN INCHES (MILLIMETERS) UNLESS OTHERWISE SHOWN.

| | | | | | | | | | | | | | |
|---|-------------------------------|-----------------|------------------------------------|---|---|-------------|------|------------------------|---------------------------|------------------|-----------------------|--------------------|--------------------|
| FILE NAME = W:\dists\td\22x34\to22.dgn | USER NAME = goglianob | DESIGNED - - | REVISED - R. MIRS 09-16-97 | STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION | ARTERIAL ROAD INFORMATION SIGN | | | F.A.U. RTE. 1397 | SECTION 13-00181-00-R5 | COUNTY DUPAGE | TOTAL SHEETS 26 | SHEET NO. 24 | |
| | PLOT SCALE = 3/8" = 1' IN. | DRAWN - - | REVISED - R. MIRS 12-11-97 | | SCALE: NONE | SHEET NO. 1 | OF 1 | SHEETS | STA. | TO STA. | TC-22 | | CONTRACT NO. 63833 |
| | PLOT DATE = 1/4/2008 | CHECKED - - | REVISED - T. RAMMACHER 02-02-99 | | FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT | | | | | | | | |
| | | DATE - - | REVISED - C. JUICIUS 01-31-07 | | | | | | | | | | |