

CONST.
CODE
100%
STATE
0014

SUMMARY OF QUANTITIES

PAY ITEM NO.	DESCRIPTION	UNIT	QUANTITY
30300104	AGGREGATE SUBGRADE IMPROVEMENT, 4"	SQ YD	170
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	24
40600990	TEMPORARY RAMP	SO YD	24
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	97
42001500	P.C. CONCRETE BRIDGE APPROACH SHOULDER PAVEMENT	SO YD	147
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SO YD	89
44004250	PAVED SHOULDER REMOVAL	SO YD	161
44213200	SAW CUTS	FOOT	137
48300500	PORTLAND CEMENT CONCRETE SHOULDERS 10"	SO YD	22
50102400	CONCRETE REMOVAL	CU YD	23
50300100	FLOOR DRAINS	EACH	116
50300255	CONCRETE SUPERSTRUCTURE	CU YD	27.1
50300260	BRIDGE DECK GROOVING	SO YD	4382
50300300	PROTECTIVE COAT	SO YD	915
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	9830
50606701	CLEANING AND PAINTING STRUCTURAL STEEL, LOCATION 1	L SUM	1
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	18,774
50800515	BAR SPLICERS	EACH	68
52000110	PREFORMED JOINT STRIP SEAL	FOOT	189
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	6
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	18
52100030	ELASTOMERIC BEARING ASSEMBLY, TYPE III	EACH	6

22
• SPECIALTY ITEMS

CONST.
CODE
100%
STATE
0014

SUMMARY OF QUANTITIES

PAY ITEM NO.	DESCRIPTION	UNIT	QUANTITY
52100520	ANCHOR BOLTS, 1"	EACH	72
52100530	ANCHOR BOLTS, 1/4"	EACH	48
52100540	ANCHOR BOLTS, 1/2"	EACH	24
58700300	CONCRETE SEALER	SO FT	2940
59000200	EPOXY CRACK INJECTION	FOOT	49
60260100	INLETS TO BE ADJUSTED	EACH	4
63300575	REMOVE AND REERECT RAIL ELEMENT OF EXISTING GUARDRAIL	FOOT	75
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3
67100100	MOBILIZATION	L SUM	1
70100207	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402	EACH	1
70100800	TRAFFIC CONTROL AND PROTECTION, STANDARD 701401	L SUM	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	5
70300100	SHORT TERM PAVEMENT MARKING	FOOT	336
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	9460
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	2384
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1356
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	1305
70600250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1
70600350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1
78009004	MODIFIED URETHANE PAVEMENT MARKING - LINE 4"	FOOT	3450

20

HBM
ENGINEERING GROUP, LLC
CORPORATE FINANCIAL & DESIGN
INSPECTION & TESTING
RESEARCH & TESTING

4415 WEST HARRISON ST.
SUITE 231
HILLSIDE, IL 60162
PHONE: (708) 236-0900
FAX: (708) 236-0901

DESIGNED - JMG	REVISED -
CHECKED - MJ	REVISED -
DRAWN - HH	REVISED -
CHECKED - JMG, MAI	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES (SHEET 1 OF 2)
EB US ROUTE 20 OVER PEGATONICA RIVER STRUCTURE NO. 089-0042
SHEET NO. 1 OF 2 SHEETS

Rev. 6-5-13
F.A.P. SECTION COUNTY TOTAL SHEETS SHEET NO.
0301 (177-4B-13M) STEPHENSON 43 3
CONTRACT NO. 64J24
ILLINOIS FED. AID PROJECT