

CONST.
CODE
100%
STATE
0014

SUMMARY OF QUANTITIES

	DESCRIPTION	UNIT	QUANTITY
• 78009006	MODIFIED URETHANE PAVEMENT MARKING - LINE 6"	FOOT	300
• 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	4
78300100	PAVEMENT MARKING REMOVAL	SQ FT	750
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	4
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	334
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	11
Z0001903	STRUCTURAL STEEL REMOVAL	POUND	9170
Z0001905	STRUCTURAL STEEL REPAIR	POUND	12330
Z0003802	REMOVAL OF EXISTING BEARINGS	EACH	25
Z0006012	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	4533
Z0007112	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES	L SUM	1
Z0010400	CLEANING BRIDGE SEATS	SQ FT	532
Z0012130	BRIDGE DECK SCARIFICATION, 3/4"	SQ YD	4533
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	459
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	83
Z0015802	PLUG EXISTING DECK DRAINS	EACH	68
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ YD	51
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	165
Z0038117	PORTLAND CEMENT CONCRETE SURFACE REMOVAL 1"	SQ YD	734
Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	25

20
• SPECIALTY ITEMS

HBM
ENGINEERING GROUP, LLC
CONSULTING & DESIGN
INSPECTION & TESTING
RESEARCH & TESTING
4415 WEST HARRISON ST.
SUITE 231
HILLSIDE, IL 60162
PHONE: (708) 236-0900
FAX: (708) 236-0901

DESIGNED - JMG	REVISED -
CHECKED - MJ	REVISED -
DRAWN - HH	REVISED -
DATE - 03/13/2013	CHECKED - JMG, MAI
	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES (SHEET 2 OF 2)
EB US ROUTE 20 OVER PECATONICA RIVER STRUCTURE NO. 089-0042

F.A.P. RTE. 0301	SECTION (177-4B-11M)	COUNTY STEPHENSON	TOTAL SHEETS 43	SHEET NO. 4
CONTRACT NO. 64J24			ILLINOIS FED. AID PROJECT	

SHEET NO. 2 OF 2 SHEETS