

HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70						40603340	STAGE
STATION	STATION	WIDTH FOOT	AREA SQ-YD	THICKNESS INCH	WEIGHT TON		
904+87.50	905+27.50	10	48.9	2	5		Prestage 1
914+69.50	915+09.50	10	48.9	2	5		Stage 1
904+27.50	904+52.50	34	94.5	1.5	8		
904+52.50	904+77.50	34	94.5	1.75	9.3		
904+77.50	905+02.50	34	94.5	1.5	8		
905+02.50	905+27.50	34	94.5	1.5	8		
914+69.50	914+94.50	34	94.5	1.5	8		
914+94.50	915+19.50	34	94.5	1.5	8		
915+19.50	915+44.50	34	94.5	1.75	9.3		
915+44.50	915+69.50	34	94.5	1.5	8		Stage 2
904+27.50	904+52.50	10	27.8	1.5	2.4		
904+52.50	904+77.50	10	27.8	1.75	3.0		
904+77.50	905+02.50	10	27.8	1.5	2.4		
905+02.50	905+27.50	10	27.8	1.5	2.4		
914+69.50	914+94.50	10	27.8	1.5	2.4		
914+94.50	915+19.50	10	27.8	1.5	2.4		
915+19.50	915+44.50	10	27.8	1.75	3.0		
915+44.50	915+69.50	10	27.8	1.5	2.4		
TOTAL						97	

HOT-MIX ASPHALT SURFACE REMOVAL, 2"				44000157	COMMENT
STATION	STATION	WIDTH FOOT	AREA SQ-YD		
904+87.50	905+27.50	10	44.5		Left Shoulder
914+69.50	915+09.50	10	44.5		Left Shoulder
TOTAL				89	

PAVED SHOULDER REMOVAL			44004250
STATION	STATION	AREA SQ-YD	
904+91.50	905+27.50	42.3	
914+69.50	915+06.50	43.5	
904+95.50	05+27.50	37.6	
914+69.50	915+01.50	37.6	
TOTAL			161

SAW CUTS			44213200	COMMENT
STATION	STATION	LENGTH FOOT		
904+91.50	905+27.50	36.00		Right EOP
914+69.50	915+06.50	37.00		Right EOP
904+95.50	905+27.50	32.00		Left EOP
914+69.50	915+01.50	32.00		Left EOP
TOTAL			137.00	

PORTLAND CEMENT CONCRETE SHOULDER 10"				48300500
STATION	STATION	WIDTH FOOT	AREA SQ-YD	
904+91.50	904+97.50	13	8.7	
914+99.50	915+06.50	10	7.8	
904+95.50	904+97.50	13	2.9	
914+99.50	915+01.50	10	2.3	
TOTAL				22

INLETS TO BE ADJUSTED		60260100	COMMENT
STATION	EACH		
905+13.50	1		
914+83.50	1		Left Shoulder
905+13.50	1		Left Shoulder
914+83.50	1		Right Shoulder
TOTAL		4	

WORKZONE PAVEMENT MARKING REMOVAL				70301000	STAGE
STATION	STATION	WIDTH INCH	AREA SQ-FT		
885+50.00	904+27.50	4	625.80		Stage 1
900+52.50	904+27.50	4	125.00		
915+81.00	918+81.00	4	100.00		
885+50.00	915+80.81	4	1010.30		Stage 2
901+82.50	917+51.00	4	522.80		
TOTAL				2384	

TEMPORARY CONCRETE BARRIER			70400100	STAGE
STATION	STATION	LENGTH FOOT		
902+25.12	915+80.81	1356		Stage 1
TOTAL			1356	

RELOCATE CONCRETE BARRIER				70400200
STATION	STATION	LENGTH FOOT	STAGE	
902+75.80	915+80.80	1305		Stage 2
TOTAL			1305	

RAISED REFLECTIVE PAVEMENT MARKER				78100100
LOCATION				EACH
North Bridge approach				2
South Bridge approach				2
TOTAL				4

MODIFIED URETHANE PAVEMENT MARKING - LINE 4"			78009004	COMMENT
STATION	STATION	LENGTH FOOT		
900+52.50	918+81.00	1829		Left EOP
901+82.50	917+51.00	1569		Right EOP
			52	Nominal quantity as needed and directed by RE
TOTAL			3450	

MODIFIED URETHANE PAVEMENT MARKING - LINE 6"				78009006 (FOOT)	COMMENT
STATION	STATION	GROSS LENGTH FOOT	NET LENGTH 10' PER 40'		
904+27.50	915+69.50	1142.00	286		30 skip - 10 dash
			14		Nominal quantity as need and directed by RE
TOTAL			300		


RAISED REFLECTIVE PAVEMENT MARKER REMOVAL		78300200
LOCATION		EACH
North Bridge approach		2
South Bridge approach		2
TOTAL		4

PAVEMENT MARKING REMOVAL					78300100	COMMENT
STATION	STATION	LENGTH FOOT	WIDTH INCH	AREA SQ-FT		
900+52.50	918+81.00	1828.50	4	610		Stage I Left edge line
901+82.50	904+27.50	245.00	4	80		Stage II Right edge line
915+69.50	917+51.00	181.50	4	60		Stage II Right edge line
TOTAL					750	

PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)					x4400100
STATION	STATION	LENGTH FOOT	WIDTH FOOT	AREA SQ-YD	
904+27.50	904+52.50	25	44	122.3	
915+69.50	915+44.50	25	44	122.3	
904+87.50	905+27.50	40	10	44.5 *	
914+69.50	915+09.50	40	10	44.5 *	
TOTAL					334

* Nominal Quantity for PreStage 1 North and South Left Shoulder Improvements Field Verify

PORTLAND CEMENT CONCRETE SURFACE REMOVAL 1"					Z0038117
STATION	STATION	LENGTH FOOT	WIDTH FOOT	AREA SQ-YD	
904+52.50	905+27.50	75	44	367	
915+44.50	914+69.50	75	44	367	
TOTAL					734



4415 WEST HARRISON ST.
SUITE 231
MILLSBORO, IL 62162
PHONE: (708) 236-0900
FAX: (708) 236-0901

DESIGNED - JMG	REVISED -
CHECKED - MI	REVISED -
DRAWN - HH	REVISED -
CHECKED - JMG, MAI	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
EB US ROUTE 20 OVER PECATONICA RIVER STRUCTURE NO. 089-0042
SHEET NO. 1 OF 2 SHEETS

F.A.P. RTE. 0301	SECTION (177-48-11M)	COUNTY STEPHENSON	TOTAL SHEETS 43	SHEET NO. 5
CONTRACT NO. 64J24				ILLINOIS FED. AID PROJECT

DATE - 03/13/2013