

GUARD RAIL SCHEDULE							
STA. - STA.	LT	RT	GUARDRAIL REMOVAL	LONG-SPAN GUARDRAIL OVER CULVERT	REMOVE & RE-ERECT STEEL PLATE BEAM GUARDRAIL, TYPE A	REMOVE & RE-ERECT TRAFFIC BARRIER TERMINAL, TYPE 1	GUARDRAIL MARKERS, TYPE A
KENDALL COUNTY			FOOT	FOOT	FOOT	FOOT	EACH
LOCATION 3							
1120+08 - 1121+48		X					4
1120+28 - 1121+68	X						4
1120+45 - 1120+69	X						
1120+45 - 1120+69		X					
1120+69 - 1121+07	X		38	38			
1120+69 - 1121+07		X	38	38			
1121+07 - 1121+32	X						
1121+07 - 1121+32		X					
TOTALS			76	76			8

EARTHWORK SCHEDULE										
STA. - STA.	LT	RT	TOPSOIL EXCAVATION & PLACEMENT	BRACED EXCAVATION	SEEDING, CLASS 2A	NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT	PERIMETER EROSION BARRIER	HEAVY DUTY EROSION CONTROL BLANKET
KENDALL COUNTY			CU YD	CU YD	ACRE	POUND	POUND	POUND	FOOT	SQ YD
LOCATION 3										
1120+45 - 1121+15	X		5	33	0.01	0.9	0.9	0.9	100	75
1120+45 - 1121+15		X	5	33	0.01	0.9	0.9	0.9	100	75
LOCATION 4										
1360+51 - 1361+21	X		5	39	0.01	0.9	0.9	0.9	100	74
1360+51 - 1361+21		X	5	39	0.01	0.9	0.9	0.9	100	74
LOCATION 5										
1390+80 - 1391+50		X	6	54	0.01	0.9	0.9	0.9	100	92
1391+10 - 1391+80	X		6	54	0.01	0.9	0.9	0.9	100	92
LOCATION 6										
1395+00 - 1395+70	X		6	50	0.01	0.9	0.9	0.9	100	97
1396+30 - 1397+00		X	6	50	0.01	0.9	0.9	0.9	100	97
TOTALS			44	352	0.8	7.2	7.2	7.2	800	676

BARRIER WALL SCHEDULE						
STA.-STA.	LT	RT	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS	RELOCATE IMPACT ATTENUATORS
KENDALL COUNTY			FOOT	FOOT	EACH	EACH
LOCATION 3						
1120+06 - 1121+70	X			138		2
1120+06 - 1121+70		X		138		2
LOCATION 4						
1360+04 - 1361+68	X			138		2
1360+04 - 1361+68		X		138		2
LOCATION 5						
1390+48 - 1392+12	X			138		2
1390+48 - 1392+12		X		138		2
LOCATION 6						
1395+68 - 1397+52	X			138		2
1395+68 - 1397+52		X		138		2
TOTALS				1104		16