CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODES: 80% FED. 20% STATE — ROADWAY 0004 RURAL	BRIDGE 0011 SN 090-0178	100% STATE — MOWING 0004
48203100	HOT-MIX ASPHALT SHOULDERS	TON	441	441		
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1		1	
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1		1	
50200100	STRUCTURE EXCAVATION	CU YD	258		258	
50200300	COFFERDAM EXCAVATION	CU YD	353		353	
50201121	COFFERDAM (TYPE 2) (LOCATION - 1)	EACH	1		1	
50201122	COFFERDAM (TYPE 2) (LOCATION - 2)	EACH	1		1	
50300100	FLOOR DRAINS	EACH	6		6	
50300225	CONCRETE STRUCTURES	CU YD	170.0		170.0	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	364.5		364.5	
50300260	BRIDGE DECK GROOVING	SQ YD	940		940	
50300265	SEAL COAT CONCRETE	CU YD	106.2		106.2	
50300280	CONCRETE ENCASEMENT	CU YD	4.2		4.2	
50300300	PROTECTIVE COAT	SQ YD	1177		1177	

* SPECIALTY ITEM

TERRA ENGINEERING LTD.

USER NAME = NI	DESIGNED - CL	REVISED -
	DRAWN - KJC	REVISED -
PLOT SCALE = N/A	CHECKED - LVA	REVISED -
PLOT DATE = 3/19/2013	DATE - 03/20/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL 9 OVER MUD CREEK

SCALE: N/A | SHEET NO. 3 OF 7 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	(119BR) BR	TAZEWELL	80	6

CONTRACT NO. 68757
ILLINOIS FED. AID PROJECT

ILDOT_PDF40_mPDF5_Bw.shtcfg Interra Bentley V8i\Standards\ILDOT\ldot5tcf\tables\pen\PLOTLABEL.TBL
M:\IL RT 9 OVER MUD CREEK\CIVIL\CADD Sheets\D468757-sht-200.dgn