CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODES: 80% FED. 20% STATE — ROADWAY 0004 RURAL	BRIDGE 0011 SN 090-0178	100% STATE — MOWING 0004
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		1	
50500505	STUD SHEAR CONNECTORS	EACH	4824		4824	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	111580		111580	
50800515	BAR SPLICERS	EACH	989		989	
51201600	FURNISHING STEEL PILES HP12X53	FOOT	600		600	
51201800	FURNISHING STEEL PILES HP14X73	FOOT	610		610	
51202305	DRIVING PILES	FOOT	1210		1210	
51203600	TEST PILE STEEL HP12X53	EACH	2		2	
51203800	TEST PILE STEEL HP14X73	EACH	2		2	
51500100	NAME PLATES	EACH	1		1	
52100520	ANCHOR BOLTS, 1"	EACH	24		24	
52100530	ANCHOR BOLTS, 1 1/4"	EACH	24		24	
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	79		79	
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	650.0	650.0		

* SPECIALTY ITEM

TERRA ENGINEERING LTD.

USER NAME = hl	DESIGNED - CL	REVISED -
	DRAWN - KJC	REVISED -
PLOT SCALE = N/A	CHECKED - LVA	REVISED -
PLOT DATE = 3/19/2013	DATE - 03/20/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
IL 9 OVER MUD CREEK

SCALE: N/A | SHEET NO. 4 OF 7 SHEETS | STA. | TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	(119BR) BR	TAZEWELL	80	7

CONTRACT NO. 68757

ILLINOIS FED. AID PROJECT

MAIL RT 9 OVER MUD CREEK\CIVIL\C400 Sheets\0468757-sht-500.dgn
ILDOT.PDF-NOLAYERS.BW.pltcfg
I:\Terra Bentley\8i\Standards\IDOT\IdotStd\tables\pen\PLOTLOGEL.TBL