

I:\Terra_Bantley\B\Standards\ILDOT\dot\std\tables\perm\PL0TLABEL.TBL
 ILDOT_PDFNLAVERS.BWp1cfcg
 M:\IL RT 9 OVER MUD CREEK\CIVIL\CA00 Sheets\0468757-rt-schedule.dgn

PAVEMENT REMOVAL

ALIGNMENT:	IL RTE 9		LENGTH	WIDTH	AREA
STA		STA	FEET	FEET	SQ YD
648+19.75	TO	648+72.48	52.73	28.18	165.10
649+94.37	TO	650+77.25	82.88	27.63	254.41
			TOTAL		420

PAVEMENT BREAKING

ALIGNMENT:	IL RTE 9		LENGTH	WIDTH	AREA
STA		STA	FEET	FEET	SQ YD
650+77.25	TO	653+97.00	319.75	26.22	931.50
			TOTAL		932

HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT

ALIGNMENT:	IL RTE 9		LENGTH	WIDTH	AREA
STA		STA	FEET	FEET	SQ YD
643+00.00	TO	643+60.00	60.00	26.03	173.52
656+39.99	TO	657+00.01	60.02	26.10	174.04
			TOTAL		348

HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH

ALIGNMENT:	IL RTE 9		LENGTH	WIDTH	AREA
STA		STA	FEET	FEET	SQ YD
655+44.02	TO	656+40.00	95.98	25.77	274.83
643+60.00	TO	644+66.46	106.46	26.16	309.48
			TOTAL		584

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL

ALIGNMENT:	IL RTE 9		EACH
STA	OFFSET		
642+24.57	0.00		1
643+04.57	0.00		1
643+84.57	0.00		1
644+64.57	0.00		1
645+44.57	0.00		1
646+24.57	0.00		1
647+04.57	0.00		1
647+84.57	0.00		1
651+04.57	0.00		1
651+84.57	0.00		1
652+64.57	0.00		1
653+44.57	0.00		1
654+24.57	0.00		1
655+04.57	0.00		1
655+84.57	0.00		1
656+64.57	0.00		1
657+44.57	0.00		1
		TOTAL	17

RAISED REFLECTIVE PAVEMENT MARKER

ALIGNMENT:	IL RTE 9		EACH
STA	OFFSET		
647+85.00	0.00		1
647+05.00	0.03	RT	1
646+25.00	0.05	RT	1
645+45.00	0.07	RT	1
644+65.00	0.10	RT	1
643+85.00	0.12	RT	1
643+05.00	0.15	RT	1
642+25.00	0.17	RT	1
651+10.24	0.00		1
651+90.24	0.00		1
652+70.24	0.00		1
653+50.24	0.00		1
654+30.24	0.00		1
655+10.24	0.00		1
655+90.24	0.02	LT	1
656+70.24	0.04	LT	1
657+50.24	0.07	LT	1
		TOTAL	17

PAVEMENT MARKING REMOVAL

(4" SKIP DASH)						
ALIGNMENT:	IL RTE 9		LENGTH	WIDTH	AREA	
STA		STA	FEET	INCH	SQ FT	
642+00.00	TO	643+00.00	100.00	4.00	8.33	
657+00.01	TO	658+00.00	99.99	4.00	8.33	
				SUB TOTAL	17	
(4" SOLID)						
ALIGNMENT:	IL RTE 9		LENGTH	WIDTH	AREA	
STA		STA	FEET	INCH	SQ FT	
642+00.00	TO	645+00.00	300.00	4.00	100.00	
657+00.00	TO	658+00.00	100.00	4.00	33.33	
642+00.00	TO	658+00.00	1,600.00	4.00	533.33	
				SUB TOTAL	667	
				TOTAL	684	

MODIFIED URETHANE PAVEMENT MARKING - LINE 4"

STA	STA	FOOT
641+00	642+00	0.00
642+00	643+00	425.00
643+00	644+00	325.00
644+00	645+00	325.00
645+00	646+00	325.00
646+00	647+00	325.00
647+00	648+00	325.00
648+00	649+00	318.90
649+00	650+00	325.00
650+00	651+00	307.67
651+00	652+00	300.00
652+00	653+00	300.00
653+00	654+00	300.00
654+00	655+00	300.00
655+00	656+00	300.00
656+00	657+00	300.00
657+00	658+00	400.00
658+00	659+00	0.00
	TOTAL	5,202



USER NAME = hl	DESIGNED - CL	REVISED -
	DRAWN - KJC	REVISED -
PLOT SCALE = N/A	CHECKED - LVA	REVISED -
PLOT DATE = 3/19/2013	DATE - 03/20/13	REVISED -

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES		
IL 9 OVER MUD CREEK		
SCALE: N/A	SHEET NO. 2 OF 6 SHEETS	STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	(119BR) BR	TAZEWELL	80	14
CONTRACT NO. 68757				
ILLINOIS FED. AID PROJECT				