

I:\Terra\_Bantley\B\Standards\ILDOT\Video\Tables\perm\PL0TLABEL.tbl  
 ILDOT\_PDFNOLAYERS.BWp1.tcf.g  
 M:\IL RT 9 OVER MUD CREEK\CIVIL\CA00D Sheets\0468757-rt-schedule.dgn

**GUARDRAIL  
REMOVAL**

ALIGNMENT: STA	IL RTE 9 OFFSET			STA	OFFSET		LENGTH FOOT
647+74.74	17.31	LT	TO	648+50.59	16.77	LT	75.85
647+49.51	18.82	LT	TO	647+74.74	17.31	LT	25.27
647+49.75	18.75	RT	TO	647+75.54	16.95	RT	25.84
647+75.54	16.95	RT	TO	648+54.88	16.59	RT	79.35
650+11.83	16.57	RT	TO	650+91.47	16.77	RT	79.64
650+91.47	16.77	RT	TO	651+15.84	18.47	RT	24.43
650+91.71	16.69	LT	TO	651+16.38	18.45	LT	24.73
650+11.84	16.66	LT	TO	650+91.71	16.69	LT	79.87
						TOTAL	415

**GUARDRAIL  
MARKERS, TYPE A**

ALIGNMENT: STA	IL RTE 9 OFFSET			STA	OFFSET		EACH
646+29.51	18.06	RT					1
647+09.51	18.04	RT					1
647+89.51	18.01	RT					1
646+65.87	18.00	LT					1
647+45.87	18.00	LT					1
648+25.87	18.00	LT					1
650+74.25	18.00	RT					1
651+54.25	18.00	RT					1
652+34.25	18.00	RT					1
651+10.49	18.00	LT					1
651+90.49	18.00	LT					1
652+70.49	18.00	LT					1
						TOTAL	12

**PERMANENT SURVEY  
MARKERS, TYPE I**

ALIGNMENT: STA	IL RTE 9 OFFSET			STA	OFFSET		EACH
644+50.00	0.00						1
654+50.00	0.00						1
649+50.00	0.00						1
						TOTAL	3

**FURNISHING AND  
ERECTING RIGHT  
OF WAY MARKERS**

ALIGNMENT: STA	IL RTE 9 OFFSET			STA	OFFSET		EACH
643+00.00	42.40	LT					1
643+50.00	50.00	LT					1
645+00.00	50.00	LT					1
646+00.00	60.00	LT					1
647+25.00	60.00	LT					1
648+15.00	150.00	LT					1
650+70.00	150.00	LT					1
651+00.00	65.00	LT					1
654+00.00	65.00	LT					1
656+00.00	41.82	LT					1
657+00.00	50.00	RT					1
656+00.00	50.00	RT					1
654+00.00	65.00	RT					1
651+00.00	65.00	RT					1
650+65.00	101.00	RT					1
648+40.00	101.00	RT					1
648+00.00	60.00	RT					1
645+00.00	60.00	RT					1
643+00.00	50.00	RT					1
643+00.00	33.00	RT					1
657+00.00	33.00	RT					1
						TOTAL	21

**STEEL PLATE BEAM  
GUARDRAIL, TYPE  
A, 6 FOOT POSTS**

**TRAFFIC BARRIER  
TERMINAL, TYPE 6**

**TRAFFIC BARRIER  
TERMINAL, TYPE 1  
(SPECIAL) FLARED**

**TERMINAL MARKER  
- DIRECT APPLIED**

ALIGNMENT: STA	IL RTE 9 OFFSET			STA	OFFSET		LENGTH FOOT	EACH	EACH	EACH
645+47.00	21.21	RT								1
645+48.13	21.21	RT	TO	645+83.57	18.00	RT			1	
645+83.57	18.00	RT	TO	647+82.12	18.00	RT	198.55			
647+82.12	18.00	RT	TO	648+25.87	18.00	RT		1		
646+22.00	21.62	LT								1
646+23.13	20.78	LT	TO	646+59.51	18.00	LT			1	
646+59.51	18.00	LT	TO	647+82.12	18.00	LT	122.61			
647+82.12	18.00	LT	TO	648+25.87	18.00	LT		1		
650+74.25	18.00	RT	TO	651+18.00	18.00	RT		1		
651+18.00	18.00	RT	TO	652+40.50	18.00	RT	122.50			
652+40.50	18.00	RT	TO	652+76.87	20.78	RT			1	
652+78.00	20.37	RT								1
650+74.25	18.00	LT	TO	651+18.00	18.00	LT		1		
651+18.00	18.00	LT	TO	653+15.34	18.00	LT	197.34			
653+15.34	18.00	LT	TO	653+51.87	21.21	LT			1	
653+53.00	21.62	LT								1
						TOTAL	650.0	4	4	4



USER NAME = hl	DESIGNED - CL	REVISED -
	DRAWN - KJC	REVISED -
PLOT SCALE = N/A	CHECKED - LVA	REVISED -
PLOT DATE = 3/19/2013	DATE - 03/20/13	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES  
IL 9 OVER MUD CREEK**

SCALE: N/A SHEET NO. 3 OF 6 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	(119BR) BR	TAZEWELL	80	15
CONTRACT NO. 68757				
ILLINOIS FED. AID PROJECT				