

I:\Terra_Bentley\Bentley\Standards\ILDOT\Video\Tables\pen\PL01LABEL.TBL
 ILDOT_PDFNOLAYERS.BWp1.ctb
 M:\IL RT 9 OVER MUD CREEK\CIVIL\CADD Sheets\0468757-st-schedule.dgn

IL 9 LOCATION				FOR INFORMATION ONLY					
STA	TO	STA	LENGTH FT	EARTH EXCAVATION CU YD	EARTH EXCAVATION (WIDENING) CU YD	CHANNEL EXCAVATION CU YD	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE CU YD	EMBANKMENT CU YD	FURNISHED EXCAVATION CU YD
PRE STAGE									
642+50	TO	643+00	50	0.00	0.00	N/A	0.00	0.00	0.00
643+00	TO	643+50	50	0.00	0.00	N/A	0.00	0.00	0.00
643+50	TO	644+00	50	0.00	0.00	N/A	0.00	0.00	0.00
644+00	TO	644+50	50	8.50	1.84	N/A	7.76	21.35	13.59
644+50	TO	645+00	50	12.93	3.44	N/A	12.27	47.50	35.23
645+00	TO	645+50	50	14.01	3.22	N/A	12.92	59.09	46.17
645+50	TO	646+00	50	25.94	3.19	N/A	21.85	86.44	64.58
646+00	TO	646+50	50	28.86	3.19	N/A	24.03	107.79	83.75
646+50	TO	647+00	50	22.89	3.33	N/A	19.67	103.51	83.84
647+00	TO	647+50	50	10.39	3.51	N/A	10.42	49.21	38.79
647+50	TO	648+00	50	0.00	3.68	N/A	2.76	0.00	-2.76
648+00	TO	648+50	50	0.00	1.88	N/A	1.41	0.00	-1.41
648+50	TO	648+58	8	0.00	0.00	N/A	0.00	0.00	0.00
648+58	TO	650+42	184	0.00	7.17	N/A	5.38	0.00	-5.38
650+42	TO	650+50	8	0.00	0.64	N/A	0.48	0.00	-0.48
650+50	TO	651+00	50	0.00	3.91	N/A	2.93	0.00	-2.93
651+00	TO	651+50	50	0.21	4.02	N/A	3.17	48.34	45.17
651+50	TO	652+00	50	0.43	3.98	N/A	3.31	109.43	106.12
652+00	TO	652+50	50	1.12	3.93	N/A	3.78	122.85	119.07
652+50	TO	653+00	50	1.29	3.89	N/A	3.88	119.67	115.78
653+00	TO	653+50	50	0.70	3.88	N/A	3.44	134.81	131.37
653+50	TO	654+00	50	0.62	3.68	N/A	3.22	124.21	120.99
654+00	TO	654+50	50	0.56	3.35	N/A	2.93	95.24	92.31
654+50	TO	655+00	50	0.53	3.35	N/A	2.91	84.27	81.36
655+00	TO	655+50	50	0.27	1.71	N/A	1.49	36.33	34.85
655+50	TO	656+00	50	0.00	0.00	N/A	0.00	0.00	0.00
656+00	TO	656+50	50	0.00	0.00	N/A	0.00	0.00	0.00
656+50	TO	657+00	50	0.00	0.00	N/A	0.00	0.00	0.00
657+00	TO	657+50	50	0.00	0.00	N/A	0.00	0.00	0.00
SUBTOTALS			1500	129.24	70.78	N/A	150.02	1350.04	1200.02
STAGE 1									
642+50	TO	643+00	50	1.05	0.00	N/A	0.78	0.88	0.09
643+00	TO	643+50	50	1.75	0.00	N/A	1.31	4.97	3.66
643+50	TO	644+00	50	1.79	0.00	N/A	1.34	23.92	22.58
644+00	TO	644+50	50	1.31	1.83	N/A	2.35	44.31	41.96
644+50	TO	645+00	50	0.45	3.64	N/A	3.07	62.16	59.09
645+00	TO	645+50	50	0.87	1.81	N/A	2.01	126.60	124.59
645+50	TO	646+00	50	1.18	0.00	N/A	0.88	137.44	136.56
646+00	TO	646+50	50	1.13	0.00	N/A	0.85	87.43	86.58
646+50	TO	647+00	50	1.05	0.00	N/A	0.78	75.72	74.94
647+00	TO	647+50	50	1.30	0.00	N/A	0.97	73.44	72.47
647+50	TO	648+00	50	8.82	0.00	N/A	6.62	52.65	46.03
648+00	TO	648+50	50	71.38	0.00	N/A	53.53	28.67	-24.87
648+50	TO	648+58	8	22.89	0.00	N/A	17.17	7.02	-10.15
648+58	TO	650+42	184	421.88	0.00	N/A	316.41	182.14	-134.27
650+42	TO	650+50	8	11.63	0.00	N/A	8.72	5.92	-2.80
650+50	TO	651+00	50	31.07	0.00	N/A	23.31	93.27	69.96
651+00	TO	651+50	50	0.48	0.00	N/A	0.36	145.09	144.73
651+50	TO	652+00	50	0.47	0.00	N/A	0.35	136.41	136.05
652+00	TO	652+50	50	0.46	0.00	N/A	0.35	157.27	156.92
652+50	TO	653+00	50	0.46	0.00	N/A	0.35	175.81	175.46
653+00	TO	653+50	50	0.46	0.00	N/A	0.35	141.80	141.45
653+50	TO	654+00	50	0.53	0.00	N/A	0.40	101.77	101.37
654+00	TO	654+50	50	0.53	1.84	N/A	1.78	92.72	90.94
654+50	TO	655+00	50	0.45	3.63	N/A	3.06	81.31	78.25
655+00	TO	655+50	50	1.44	1.79	N/A	2.42	57.81	55.39
655+50	TO	656+00	50	2.68	0.00	N/A	2.01	37.56	35.55
656+00	TO	656+50	50	2.09	0.00	N/A	1.57	18.65	17.08
656+50	TO	657+00	50	2.12	0.00	N/A	1.59	4.15	2.56
657+00	TO	657+50	50	1.48	0.00	N/A	1.11	0.77	-0.34
SUBTOTALS			1500	593.20	14.54	N/A	455.80	2157.66	1701.85

IL 9 LOCATION				FOR INFORMATION ONLY					
STA	TO	STA	LENGTH FT	EARTH EXCAVATION CU YD	EARTH EXCAVATION (WIDENING) CU YD	CHANNEL EXCAVATION CU YD	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE CU YD	EMBANKMENT CU YD	FURNISHED EXCAVATION CU YD
SUBTOTALS									
STAGE 2									
642+50	TO	643+00	50	16.86	N/A	N/A	12.65	0.00	-12.65
643+00	TO	643+50	50	29.13	N/A	N/A	21.85	0.00	-21.85
643+50	TO	644+00	50	23.99	N/A	N/A	17.99	14.47	-3.52
644+00	TO	644+50	50	12.14	N/A	N/A	9.10	14.47	5.37
644+50	TO	645+00	50	0.55	N/A	N/A	0.41	0.06	-0.34
645+00	TO	645+50	50	0.29	N/A	N/A	0.22	0.41	0.19
645+50	TO	646+00	50	0.47	N/A	N/A	0.35	2.37	2.02
646+00	TO	646+50	50	0.53	N/A	N/A	0.40	3.87	3.47
646+50	TO	647+00	50	0.32	N/A	N/A	0.24	3.12	2.88
647+00	TO	647+50	50	30.44	N/A	N/A	22.83	48.31	25.49
647+50	TO	648+00	50	120.19	N/A	N/A	90.14	89.74	-0.40
648+00	TO	648+50	50	268.64	N/A	N/A	201.48	87.53	-113.95
648+50	TO	648+58	8	61.51	N/A	N/A	46.13	16.32	-29.81
648+58	TO	650+42	184	2099.00	N/A	N/A	1574.25	416.07	-1158.18
650+42	TO	650+50	8	122.15	N/A	N/A	91.61	19.45	-72.16
650+50	TO	651+00	50	544.14	N/A	N/A	408.10	126.46	-281.64
651+00	TO	651+50	50	272.94	N/A	N/A	204.71	79.86	-124.85
651+50	TO	652+00	50	91.16	N/A	N/A	68.37	24.19	-44.18
652+00	TO	652+50	50	0.00	N/A	N/A	0.00	23.03	23.03
652+50	TO	653+00	50	0.00	N/A	N/A	0.00	19.25	19.25
653+00	TO	653+50	50	0.00	N/A	N/A	0.00	23.87	23.87
653+50	TO	654+00	50	0.00	N/A	N/A	0.00	19.24	19.24
654+00	TO	654+50	50	0.00	N/A	N/A	0.00	4.92	4.92
654+50	TO	655+00	50	0.04	N/A	N/A	0.03	1.34	1.31
655+00	TO	655+50	50	0.81	N/A	N/A	0.61	25.47	24.86
655+50	TO	656+00	50	1.75	N/A	N/A	1.31	36.53	35.22
656+00	TO	656+50	50	4.81	N/A	N/A	3.61	11.26	7.65
656+50	TO	657+00	50	6.23	N/A	N/A	4.67	0.01	-4.66
657+00	TO	657+50	50	2.39	N/A	N/A	1.79	0.00	-1.79
SUBTOTALS			1500	3710.47	0.00	N/A	2782.85	1111.63	-1671.23
MUD CREEK LOCATION									
38+82	TO	39+00	18	N/A	N/A	16.23	0.00	1.09	1.09
39+00	TO	39+25	25	N/A	N/A	120.19	0.00	1.50	1.50
39+25	TO	39+50	25	N/A	N/A	268.04	0.00	0.00	0.00
39+50	TO	39+75	25	N/A	N/A	354.26	0.00	1.62	1.62
39+75	TO	40+00	25	N/A	N/A	368.38	0.00	9.55	9.55
40+00	TO	40+25	25	N/A	N/A	321.22	0.00	24.12	24.12
40+25	TO	40+50	25	N/A	N/A	270.43	0.00	40.91	40.91
40+50	TO	40+75	25	N/A	N/A	323.03	0.00	48.91	48.91
40+75	TO	41+00	25	N/A	N/A	413.38	0.00	36.41	36.41
41+00	TO	41+25	25	N/A	N/A	452.22	0.00	12.30	12.30
41+25	TO	41+50	25	N/A	N/A	334.61	0.00	13.31	13.31
41+50	TO	41+75	25	N/A	N/A	168.13	0.00	15.25	15.25
41+75	TO	42+00	25	N/A	N/A	120.97	0.00	2.04	2.04
42+00	TO	42+25	25	N/A	N/A	110.93	0.00	0.02	0.02
42+25	TO	42+50	25	N/A	N/A	72.90	0.00	0.15	0.15
42+50	TO	42+65	15	N/A	N/A	14.19	0.00	0.09	0.09
SUBTOTALS			383	N/A	N/A	3729.10	0.00	207.25	207.25
GRAND TOTALS				4435	85	3730	3390	4825	1440

NOTE: THE MATERIAL FROM THE CHANNEL EXCAVATION IS ASSUMED TO BE UNSUITABLE MATERIAL FOR EMBANKMENT.



USER NAME = hl	DESIGNED - CL	REVISED -
PLOT SCALE = N/A	DRAWN - KJC	REVISED -
PLOT DATE = 3/19/2013	CHECKED - LVA	REVISED -
	DATE - 03/20/13	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES IL 9 OVER MUD CREEK	
SCALE: N/A	SHEET NO. 4 OF 6 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	(119BR) BR	TAZEWELL	80	16
CONTRACT NO. 68757				
ILLINOIS FED. AID PROJECT				