

		MULCH, METHOD 2	EROSION CONTROL BLANKET	TEMPORARY EROSION CONTROL SEEDING		
STA	STA	(ACRE)	(SQ YD)	RATE (LBS/ACRE)	APPLICATIONS	(POUND)
641+00	642+00	0.00	0.00	100	3	0.00
642+00	643+00	0.00	0.00	100	3	0.00
643+00	644+00	0.04	530.06	100	3	45.86
644+00	645+00	0.05	563.06	100	3	48.82
645+00	646+00	0.04	578.25	100	3	49.13
646+00	647+00	0.04	580.03	100	3	48.35
647+00	648+00	0.10	665.77	100	3	72.39
648+00	649+00	0.38	83.09	100	3	120.25
649+00	650+00	0.04	1,106.97	100	3	80.18
650+00	651+00	0.19	1,216.53	100	3	133.25
651+00	652+00	0.17	642.76	100	3	92.24
652+00	653+00	0.05	695.21	100	3	58.02
653+00	654+00	0.03	808.67	100	3	59.48
654+00	655+00	0.02	844.80	100	3	57.74
655+00	656+00	0.00	724.28	100	3	45.02
656+00	657+00	0.00	639.75	100	3	39.65
657+00	658+00	0.00	0.00	100	3	0.00
658+00	659+00	0.00	0.00	100	3	0.00
TOTAL		1.25	9,679			950

LOCATION	TEMPORARY DITCH CHECKS (FOOT)	PERIMETER EROSION BARRIER (FOOT)
STA. 643+20, 35' LT	30	
STA. 643+87, 39' LT	30	
STA. 646+50, 50' LT	30	
STA. 643+00 TO STA. 649.21, RT		640
STA. 649+21, RT TO STA. 649+61, LT		375
STA. 649+56, RT TO STA. 650+09, LT		370
STA. 649+56 TO STA. 657+00, RT		760
STA. 649+85 TO STA. 657+00, LT		764
STA. 649+88 TO STA. 650+77, LT		90
TOTAL	90	2,999

NOTE: QUANTITIES FOR TEMPORARY DITCH CHECKS ARE FOR 3 INSTALLATIONS AT EACH LOCATION.



USER NAME = hl	DESIGNED - CL	REVISED -
	DRAWN - KJC	REVISED -
PLOT SCALE = N/A	CHECKED - LVA	REVISED -
PLOT DATE = 3/19/2013	DATE - 03/20/13	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES
IL 9 OVER MUD CREEK**

SCALE: N/A SHEET NO. 5 OF 6 SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
693	(119BR) BR	TAZEWELL	80	17
CONTRACT NO. 68757				
ILLINOIS FED. AID PROJECT				