

LOCATION			TEMPORARY BRIDGE TRAFFIC SIGNALS (EACH)	TEMPORARY RUMBLE STRIPS (EACH)	TEMPORARY CONCRETE BARRIER (FOOT)	RELOCATE TEMPORARY CONCRETE BARRIER (FOOT)	BARRIER WALL MARKERS TYPE C (EACH)	IMPACT ATTENUATORS, TEMP (NON-REDIRECTIVE), TEST LVL 3 (EACH)	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LVL 3 (EACH)
STA	STA	OFFSET							
STAGE I									
625+26.00		RT		1					
630+26.00		RT		1					
635+26.00		RT		1					
642+76.00	646+73.00		1						
643+75.97		RT					1		
643+75.97	655+66.95				1190.98		48		
655+66.95		RT						1	
664+23.00		LT		1					
669+23.00		LT		1					
674+23.00		LT		1					
STAGE II									
643+75.97		LT							1
643+75.97	655+66.95					1190.98			
655+66.95		LT							1
TOTAL			1	6	1191	1191	48	2	2

LOCATION			PROPERTIES		SHORT TERM PAVEMENT MARKING (FOOT)	TEMPORARY PAVEMENT MARKING - LINE 4" (FOOT)	TEMPORARY PAVEMENT MARKING - LINE 24" (FOOT)	WORK ZONE PAVEMENT MARKING - REMOVAL (SQ FT)
STA	STA	OFFSET	TYPE	COLOR				
STAGE I								
642+26.00		RT	SOLID	WHITE			12	24
642+26.00	644+40.00	CL	SKIP-DASH	YELLOW				
642+36.00	656+63.00	RT	SOLID	WHITE		1,427		476
643+92.00	655+51.00	LT	SOLID	WHITE				
643+92.00	655+51.00	LT	SOLID	WHITE		1,159		387
655+00.00	657+00.00	CL	SKIP-DASH	YELLOW				
657+23.00		LT	SOLID	WHITE			12	24
STAGE II								
642+26.00		RT	SOLID	WHITE				24
642+86.00	657+13.00	LT	SOLID	WHITE		1,427		476
644+07.00	645+15.00	RT	SOLID	WHITE				
644+07.00	655+39.00	RT	SOLID	WHITE		1,132		378
654+28.00	655+39.00	RT	SOLID	WHITE				
657+23.00		LT	SOLID	WHITE				24
STAGE III								
643+00.00	657+00.00	CL	DOTTED	YELLOW	140			
TOTAL					140	5,145	24	1,813

LOCATION			PROPERTIES		TEMPORARY RAMP (SOYD)	TEMPORARY PAVEMENT (SOYD)	TEMPORARY PAVEMENT REMOVAL (SOYD)
STA	STA	OFFSET	LENGTH	WIDTH			
PRE-STAGE							
644+10.00	644+22.00	LT	12.00	1.00			
644+22.00	644+40.00	LT	18.00	2.00			2
644+40.00	648+50.00	LT	410.00	3.00			4
650+16.00	655+03.00	LT	487.00	3.00			137
655+03.00	655+23.00	LT	20.00	2.00			163
655+23.00	655+35.00	LT	12.00	1.00			5
							2
STAGE I							
644+10.00	644+22.00	RT	12.00	1.00			
644+22.00	644+40.00	RT	18.00	2.00			2
644+40.00	645+15.00	RT	75.00	3.00			4
645+00.00	645+15.00	RT	15.00	15.00	25		25
645+10.00	645+15.00	RT	5.00	15.00	8		
647+89.87	648+19.87	RT	30.00	15.00	50		
648+14.87	648+19.87	RT	5.00	15.00	8		
650+80.25	651+17.25	RT	37.00	15.00	62		
650+80.25	650+85.25	RT	5.00	15.00	8		
654+28.00	654+63.00	RT	35.00	15.00	58		
654+28.00	654+33.00	RT	5.00	15.00	8		
654+28.00	655+03.00	RT	75.00	3.00			25
655+03.00	655+22.00	RT	19.00	2.00			5
655+22.00	655+35.00	RT	13.00	1.00			2
STAGE II							
645+00.00	645+15.00	LT	15.00	15.00	25		
645+10.00	645+15.00	LT	5.00	15.00	8		
647+89.87	648+19.87	LT	30.00	15.00	50		
648+14.87	648+19.87	LT	5.00	15.00	8		
648+26.00	648+50.00	LT	24.00	3.00			8
650+16.00	650+74.00	LT	58.00	3.00			20
650+80.25	651+17.25	LT	37.00	15.00	62		
650+80.25	650+85.25	LT	5.00	15.00	8		
654+28.00	654+63.00	LT	35.00	15.00	58		
654+28.00	654+33.00	LT	5.00	15.00	8		
TOTAL					457	376	28



USER NAME = hl	DESIGNED - CL	REVISED -
PLOT SCALE = N/A	DRAWN - KJC	REVISED -
PLOT DATE = 3/19/2013	CHECKED - LVA	REVISED -
	DATE - 03/20/13	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

<b>SCHEDULE OF QUANTITIES IL 9 OVER MUD CREEK</b>		
SCALE: N/A	SHEET NO. 6 OF 6 SHEETS	STA. TO STA.

F.A.P. RTE. 693	SECTION (119BR) BR	COUNTY TAZEWELL	TOTAL SHEETS 80	SHEET NO. 18
CONTRACT NO. 68757				
ILLINOIS FED. AID PROJECT				