

94

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				100 % STATE	
				ROADWAY	
				0004 RURAL	
20200100	EARTH EXCAVATION	CU YD	16,140	16,140	
20400800	FURNISHED EXCAVATION	CU YD	1,366	1,366	
* 25000200	SEEDING, CLASS 2	ACRE	7.50	7.5	
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	675	675	
* 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	675	675	
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	675	675	
* 25100115	MULCH, METHOD 2	ACRE	7.50	7.50	
28000200	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	50	50	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	900	900	
28000305	TEMPORARY DITCH CHECKS	FOOT	395	395	
28000500	INLET AND PIPE PROTECTION	EACH	3	3	
31100910	SUBBASE GRANULAR MATERIAL, TYPE A 12"	SQ YD	17,852	17,852	
31101900	SUBBASE GRANULAR MATERIAL, TYPE C	TON	1,337	1,337	
31200100	STABILIZED SUBBASE 4"	SO YD	12,808	12,808	

\* SPECIALTY ITEM

FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES				F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwwork\pavidot\sparkg\100216368\067	585-shr-500.dgn	DRAWN -	REVISED -						55	68-2W5-2	MONTGOMERY	124	3
	PLOT SCALE = 100.0000' / 1"	CHECKED -	REVISED -		SCALE: 1" = 20'				SHEET 1 OF 6 SHEETS		CONTRACT NO. 72505		
	PLOT DATE = Apr-11-2013 03:43:58PM	DATE -	REVISED -		TO STA.				ILLINOIS FED. AID PROJECT				