

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				100 % STATE	
				ROADWAY	
				0004	RURAL
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	3.5	3.5	
42000521	PORTLAND CEMENT CONCRETE PAVEMENT 11" (JOINTED)	SO YD	9,760	9,760	
42100380	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT 14"	SO YD	355	355	
42100615	PAVEMENT REINFORCEMENT	SO YD	355	355	
44000100	PAVEMENT REMOVAL	SO YD	10,148	10,148	
44000189	HOT MIX ASPHALT SURFACE REMOVAL, 10"	SO YD	1,427	1,427	
44003100	MEDIAN REMOVAL	SO FT	1,619	1,619	
44004250	PAVED SHOULDER REMOVAL	SO YD	3,386	3,386	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	919	919	
48203045	HOT-MIX ASPHALT SHOULDERS, 12"	SO YD	1,046	1,046	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	465	465	
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	8	8	
60100060	CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	10	10	
60107600	PIPE UNDERDRAINS 4"	FOOT	6,602	6,602	