

PCC PAVEMENT 11" JOINTED SCHEDULE						
LOCATION STATION TO STATION	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)	PCC PAVEMENT 11" JOINTED (SQ YD)		
WEIGH STATION ROAD						
STA. 10+00.00 TO STA. 12+03.45	203	16	362	362		
STA. 12+03.45 TO STA. 17+27.10	524	16 TO 34	1,455	1,455		
STUB AT 16+20.72	VARIES	VARIES	167	167		
STA. 17+27.10 TO STA. 19+56.00	229	34	865	865		
STA. 19+56.00 TO STA. 20+35.26	79	28	247	247		
STA. 20+35.26 TO STA. 21+47.55	112	16	200	200		
STA. 21+47.55 TO STA. 31+33.53	986	28	3,067	3,067		
STUB AT 25+42.00	VARIES	VARIES	294	294		
STA. 31+33.53 TO STA. 34+17.30	284	16 TO 34	788	788		
STA. 34+17.30 TO STA. 47+20.48	1,303	16	2,317	2,317		
TOTAL				9,760		

PCC & HMA SHOULDER SCHEDULE								
LOCATION STATION TO STATION	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)	HMA SHOULDER 12" (SQ YD)	PCC SHOULDERS 11" (SQ YD)			
WEIGH STATION ROAD								
OUTSIDE STA. 10+00.00 TO STA. 16+20.72	621	8	552	--	552			
STUB STA. 16+20.72 TO STA. 16+64.28	VARIES	VARIES	67	--	67			
OUTSIDE STA. 16+64.28 TO STA. 24+70.63	806	8	717	--	717			
STUB STA. 24+70.63 TO STA. 25+75.84	VARIES	VARIES	124	--	124			
OUTSIDE STA. 25+75.84 TO STA. 49+92.55	2,417	8	2,148	--	2,148			
GORE STA. 44+07.35 TO STA. 47+89.51	382	30.64 TO 1	672	--	672			
INSIDE STA. 10+00.00 TO STA. 44+07.35	3,407	4	1,514	--	1,514			
I-55								
OUTSIDE STA. 1850+18.64 TO STA. 1859+60.06	941	10	1,046	1,046	--			
SUB-TOTAL				1,046	5,793			
TOTAL				1,046	5,793			

MEDIAN SCHEDULE				
LOCATION STATION TO STATION	LENGTH (FT)	WIDTH (FT)	MEDIAN REMOVAL (SQ FT)	CONCRETE MEDIAN TY. SB-6.06 (SQ FT)
WEIGH STATION ROAD				
STA. 19+56.00 TO STA. 22+25.85	270	6	1,619	--
STA. 19+56.00 TO STA. 31+60.00	1,204	VARIES	--	7,200
TOTAL			1,619	7,200

TEMPORARY PAVEMENT SCHEDULE					
LOCATION STATION TO STATION	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)	PAVEMENT REMOVAL (SQ YD)	TEMPORARY PAVEMENT 11" (SQ YD)
WEIGH STATION ROAD					
STA. 18+42.00 TO STA. 18+75.00	33	10	37	37	37
STA. 23+01.00 TO STA. 23+33.00	32	10	36	36	36
SUB-TOTAL				72	72
TOTAL				72	72

CONTINUOUSLY REINFORCED PCC PAVEMENT SCHEDULE						
LOCATION STATION TO STATION	LENGTH (FT)	WIDTH (FT)	AREA (SQ YD)	PAVEMENT REINFORCEMENT (SQ YD)	CONT. REIN. PCC PVT. 14" (SQ YD)	
WEIGH STATION ROAD						
STA. 47+20.66 TO STA. 47+89.51	69	6.5 TO 1	29	29	29	
STA. 47+20.01 TO STA. 47+89.51	70	16	124	124	124	
STA. 47+89.51 TO STA. 49+92.55	203	17.0 TO 1	203	203	203	
SUB-TOTAL				355	355	
TOTAL				355	355	

PAVEMENT REMOVAL SCHEDULE			
LOCATION STATION TO STATION	LOCATION	PAVED SHOULDER REMOVAL (SQ YD)	PCC REMOVAL (SQ YD)
WEIGH STATION ROAD			
STA. 10+00.00 TO STA. 49+92.00	RT & LT	3,386	10,148
SUB-TOTAL		3,386	10,148
TOTAL		3,386	10,148