

AGGREGATE SHOULDERS TYPE B					
LOCATION STATION TO STATION		LENGTH (FT)	WIDTH (FT)	QUANTITY (TONS)	
WEIGH STATION ROAD					
OUTSIDE SHOULDER					
STA. 10+00.00	TO STA. 16+09.21	609	5	87	
OUTSIDE STUB 15+99.74		12	5	2	
OUTSIDE STUB 16+42.29		52	5	7	
STA. 16+82.55	TO STA. 18+44.66	162	5	23	
STA. 19+13.55	TO STA. 20+14.03	100	5	14	
STA. 21+05.04	TO STA. 22+69.47	164	5	23	
OUTSIDE STUB 23+68.45		195	5	28	
OUTSIDE STUB 25+97.17		5	5	1	
STA. 25+94.33	TO STA. 49+92.55	2398	5	342	
INSIDE SHOULDER					
STA. 10+00.00	TO STA. 44+07.35	3407	2	259	
I-55					
OUTSIDE SHOULDER					
STA. 1850+18.64	TO STA. 1859+60.06	941	5	134	
				SUB TOTAL	919
				TOTAL	919

URETHANE PAVEMENT MARKING									
LOCATION STATION TO STATION		LENGTH (FT)	URETHANE LINE 5" (FT)		URETHANE LINE 8" (FT)		URETHANE LINE 12" (FT)		
WEIGH STATION ROAD			WHITE	YELLOW	WHITE	YELLOW	WHITE	YELLOW	
STA. 10+00.00	TO STA. 15+06.57	507	507	507	-	-	-	-	
STA. 15+06.58	TO STA. 32+28.61	1,722	4130	1722	1037	-	177	-	
STA. 32+28.61	TO STA. 44+07.02	1,178	1178	1178	-	-	-	-	
STA. 44+07.02	TO STA. 49+92.55	586	586	-	790	-	204	-	
I-55									
STA. 1847+34.00	TO STA. 1868+74.00	2,140	2675	2140					
			TOTAL	9,076	5,547	1,827	-	381	-

PIPE UNDERDRAINS						
STATION TO STATION		LOCATION (LT & RT)	PIPE UNDERDRAINS 4" (FT)	PIPE UNDERDRAINS 4" (SPECIAL) (FT)	CONCRETE HEADWALLS FOR PIPE DRAINS (EACH)	
WEIGH STATION ROAD						
STA. 10+00.00	TO STA. 12+00.00	LT	200	25	1	
STA. 12+00.00	TO STA. 16+20.00	LT	420	25		
STA. 23+60.00	TO STA. 25+25.00	LT	165	25	1	
STA. 25+75.00	TO STA. 28+00.00	LT	225	25		
STA. 28+00.00	TO STA. 31+00.00	LT	300	25	1	
STA. 31+00.00	TO STA. 34+00.00	LT	300	25	1	
STA. 34+00.00	TO STA. 37+00.00	LT	300	25	1	
STA. 37+00.00	TO STA. 40+00.00	LT	300	25	1	
STA. 40+00.00	TO STA. 43+00.00	LT	300	25	1	
STA. 43+00.00	TO STA. 46+00.00	LT	300	25	1	
STA. 46+00.00	TO STA. 49+92.00	LT	392	25	1	
STA. 10+00.00	TO STA. 17+37.00	RT	737	5		
STA. 17+37.00	TO STA. 21+87.00	RT	450	5		
STA. 21+87.00	TO STA. 25+00.00	RT	313	25	1	
STA. 25+00.00	TO STA. 27+81.00	RT	281	25		
STA. 27+81.00	TO STA. 30+34.00	RT	253	25		
STA. 30+34.00	TO STA. 34+00.00	RT	366	25		
STA. 34+00.00	TO STA. 37+00.00	RT	300	40		
STA. 37+00.00	TO STA. 40+00.00	RT	300	40		
STA. 40+00.00	TO STA. 44+00.00	RT	400	40		
TOTAL			6602	505	10	