



- LEGEND**
- ⊕ EXISTING LIGHTING UNIT TO REMAIN
 - ⊕ R EXISTING LIGHTING UNIT TO BE RELOCATED
 - ⊕ RELOCATED LIGHTING UNIT
 - LIGHT POLE, ALUMINUM, 45 FT. M.H., 15 FT. DAVIT ARM WITH 250W HORIZONTAL MOUNT HPS LUMINAIRE
 - EXISTING UNIT DUCT TO REMAIN
 - UNIT DUCT, SIZE AS INDICATED
 - ==== UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2 1/2" DIA. SCHEDULE 80 UNLESS NOTED OTHERWISE

- CABLE / CONDUIT SCHEDULE**
- (A) UNIT DUCT, 600V, 2-1C NO. 2, 1/C NO. 4 GROUND, (XLP-TYPE USE) 1 1/4" DIA. POLYETHYLENE
 - (B) UNIT DUCT, 600V, 2-1C NO. 8, 1/C NO. 8 GROUND, (XLP-TYPE USE) 3/4" DIA. POLYETHYLENE
 - (C) UNIT DUCT, 600V, 2-1C NO. 4, 1/C NO. 6 GROUND, (XLP-TYPE USE) 1" DIA. POLYETHYLENE

FILE NAME * c:\pwwork\psidot\sparksgw\0216368\087	USER NAME * sparksgw	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	LIGHTING DETAILS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE * 40.0000 1/16"	CHECKED -	REVISED -			55	68-ZWS-2	MONTGOMERY	124	82
	PLOT DATE * Apr-11-2013 03:58:57PM	DATE -	REVISED -			SCALE:	SHEET 3 OF 9 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT
	CONTRACT NO. 72505									