



- LEGEND**
- E EXISTING LIGHTING UNIT TO REMAIN
 - R EXISTING LIGHTING UNIT TO BE RELOCATED
 - RELOCATED LIGHTING UNIT
 - LIGHT POLE, ALUMINUM, 45 FT. M.H., 15 FT. DAVIT ARM WITH 250W HORIZONTAL MOUNT HPS LUMINAIRE
 - EXISTING UNIT DUCT TO REMAIN
 - UNIT DUCT, SIZE AS INDICATED
 - UNDERGROUND CONDUIT, COILABLE NONMETALLIC CONDUIT, 2 1/2" DIA.

- CABLE / CONDUIT SCHEDULE**
- A UNIT DUCT, 600V, 2-1C No. 2, 1/C NO. 4 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE
 - B UNIT DUCT, 600V, 2-1C No. 8, 1/C NO. 8 GROUND, (XLP-TYPE USE) 3/4" DIA. POLYETHYLENE
 - C UNIT DUCT, 600V, 2-1C No. 4, 1/C NO. 6 GROUND, (XLP-TYPE USE) 1" DIA. POLYETHYLENE

FILE NAME c:\p\work\p\idoc\sparksg\0216368\067	USER NAME sparksg	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	LIGHTING DETAILS		F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	585-ent-light.dgn	DRAWN -	REVISED -				55	68-2WS-2	MONTGOMERY	124	86
Default	PLOT SCALE 40.0000 1/2 in.	CHECKED -	REVISED -		SCALE:	SHEET 7 OF 9 SHEETS	STA.	TO STA.	CONTRACT NO. 72505		
	PLOT DATE Apr-11-2013 03:50:59PM	DATE -	REVISED -		ILLINOIS FED. AID PROJECT						