


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE							
				90% FED 10% STATE FAI 72 ROADWAY 0004 RURAL	90% FED 10% STATE STRUCTURE SN 084-0160 0014	90% FED 10% STATE STRUCTURE SN 084-0162 0014	90% FED 10% STATE STRUCTURE SN 084-0163 0014	90% FED 10% STATE STRUCTURE SN 084-0164 0014			
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	530	530							
28200200	FILTER FABRIC	SQ YD	455	455							
35501316	HOT-MIX ASPHALT BASE COURSE, 8"	SQ YD	56	56							
35501332	HOT-MIX ASPHALT BASE COURSE, 12"	SQ YD	1772	1772							
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	103.8	103.8							
40600300	AGGREGATE (PRIME COAT)	TON	546	546							
40600895	CONSTRUCTING TEST STRIP	EACH	2	2							
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	280	280							
40600990	TEMPORARY RAMP	SQ YD	542	542							
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	39128	39128							
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	73		73						
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	14450	14450							
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	100	100							
42001300	PROTECTIVE COAT	SQ YD	1804	1804							

FILE NAME *	USER NAME *	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
...0672C88-ahs-S00-000b.DGN		DRAWN -	REVISED -					72	(84-10-3)RS-5	SANGAMON	95	3
 Johnson, Depp & Oulsenberry CONSULTING ENGINEERS Springfield, Illinois	PLOT SCALE * 20.0000 ' / in.	CHECKED -	REVISED -		SCALE:	SHEET NO. 1 OF	SHEETS	STA.	TO STA.	CONTRACT NO. 72C88		
	PLOT DATE * 04/02/2013 08:45:53	DATE -	REVISED -							ILLINOIS FED. AID PROJECT		