


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE									
				90% FED 10% STATE	FAI 72 ROADWAY 0004 RURAL								
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	23.8	23.8									
40600300	AGGREGATE (PRIME COAT)	TON	125	125									
40600895	CONSTRUCTING TEST STRIP	EACH	0.50	0.50									
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	70	70									
40600990	TEMPORARY RAMP	SQ YD	88	88									
40603240	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	8783	8783									
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	3398	3398									
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	23094	23094									
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	26699	26699									
44000169	HOT-MIX ASPHALT SURFACE REMOVAL, 5"	SQ YD	10635	10635									
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1187	1187									
48203100	HOT-MIX ASPHALT SHOULDERS	TON	4466	4466									
63500105	DELINEATORS	EACH	43	43									
64200116	SHOULDER RUMBLE STRIPS, 16 INCH	FOOT	28150	28150									

FILE NAME = ... \CADD\0672C88-sh1-S00.DGN	USER NAME =	DESIGNED -	REVISED -
 Johnson, Depp & Quisenberry CONSULTING ENGINEERS Springfield, Illinois	PLOT SCALE = 20.0000' / in.	DRAWN -	REVISED -
	PLOT DATE = 04/02/2013 10:01:43	CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. 1 OF	SHEETS	STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	(84-10-3)RS-5	SANGAMON	95	13
CONTRACT NO. 72C88			ILLINOIS FED. AID PROJECT	