


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE							
				90% FED 10% STATE FAI 72 ROADWAY 0004 RURAL	90% FED 10% STATE STRUCTURE SN 084-0160 0014	90% FED 10% STATE STRUCTURE SN 084-0162 0014	90% FED 10% STATE STRUCTURE SN 084-0163 0014	90% FED 10% STATE STRUCTURE SN 084-0164 0014			
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	1776	1776							
44000100	PAVEMENT REMOVAL	SQ YD	1444	1444							
44000153	HOT-MIX ASPHALT SURFACE REMOVAL, 1"	SQ YD	75583	75583							
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	5090	5090							
44000162	HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4"	SQ YD	126233	126233							
44004250	PAVED SHOULDER REMOVAL	SQ YD	2724	2724							
44200529	CLASS A PATCHES, TYPE II, 8 INCH	SQ YD	250	250							
44200533	CLASS A PATCHES, TYPE III, 8 INCH	SQ YD	75	75							
44200982	CLASS B PATCHES, TYPE II, 11 INCH	SQ YD	75	75							
44201299	DOWEL BARS 1 1/2"	EACH	200	200							
44213000	PATCHING REINFORCEMENT	SQ YD	325	325							
44213200	SAWCUTS	FOOT	2595	2595							
48101200	AGGREGATE SHOULDERS, TYPE B	TON	4517	4517							
48203100	HOT-MIX ASPHALT SHOULDERS	TON	16565	16565							

FILE NAME = ... \CADD\0672C88-shr-S00.DGN	USER NAME =	DESIGNED -	REVISED -
 Johnson, Depp & Quisenberry CONSULTING ENGINEERS Springfield, Illinois	PLOT SCALE = 20.0000' / in.	DRAWN -	REVISED -
	PLOT DATE = 04/03/2013 16:25:35	CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. 2 OF	SHEETS	STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	(84-10-3)RS-5	SANGAMON	95	32
CONTRACT NO. 72C88			PART B - SHEET 4 of 67	
ILLINOIS FED. AID PROJECT				