


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE							
				90% FED 10% STATE FAI 72 ROADWAY 0004 RURAL	90% FED 10% STATE STRUCTURE SN 084-0160 0014	90% FED 10% STATE STRUCTURE SN 084-0162 0014	90% FED 10% STATE STRUCTURE SN 084-0163 0014	90% FED 10% STATE STRUCTURE SN 084-0164 0014			
50105220	PIPE CULVERT REMOVAL	FOOT	384	384							
50157300	PROTECTIVE SHIELD	SQ YD	140		140						
50300225	CONCRETE STRUCTURES	CU YD	50.6				25.3	25.3			
50300255	CONCRETE SUPERSTRUCTURE	CU YD	237.6				118.8	118.8			
50300260	BRIDGE DECK GROOVING	SQ YD	1778				889	889			
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	3426				1713	1713			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	60960				30480	30480			
50800515	BAR SPLICERS	EACH	444				222	222			
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	12				6	6			
52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	12				6	6			
52100520	ANCHOR BOLTS, 1"	EACH	48				24	24			
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	868		868						
54215547	METAL END SECTIONS 12"	EACH	4	4							
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	108	108							

FILE NAME =	USER NAME =	DESIGNED -	REVISED -
... \CADD\0672C88-sh1-S00.DGN		DRAWN -	REVISED -
 Johnson, Depp & Quisenberry CONSULTING ENGINEERS Springfield, Illinois	PLOT SCALE = 20.0000' / in.	CHECKED -	REVISED -
	PLOT DATE = 04/02/2013 10:10:01	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE:	SHEET NO. 3 OF	SHEETS	STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	(84-10-3)RS-5	SANGAMON	95	33
ILLINOIS FED. AID PROJECT			CONTRACT NO. 72C88	