

SHOULDER RUMBLE STRIPS, 16 INCH		
LOCATION	SIDE	FOOT
I-72		
LT. STA. 607+45 TO LT. STA. 699+58	OUTSIDE	9213
LT. STA. 607+45 TO LT. STA. 685+40	MEDIAN	7795
RT. STA. 607+45 TO RT. STA. 685+40	MEDIAN	7795
RT. STA. 607+45 TO RT. STA. 702+00	OUTSIDE	9455
LT. STA. 711+50 TO LT. STA. 732+40	OUTSIDE	2090
LT. STA. 686+00 TO LT. STA. 761+25	MEDIAN	7525
RT. STA. 686+00 TO RT. STA. 761+25	MEDIAN	7525
RT. STA. 708+70 TO RT. STA. 733+00	OUTSIDE	2430
LT. STA. 739+05 TO LT. STA. 798+09	OUTSIDE	5904
LT. STA. 761+80 TO LT. STA. 798+09	MEDIAN	3629
RT. STA. 761+80 TO RT. STA. 798+09	MEDIAN	3629
RT. STA. 744+60 TO RT. STA. 798+09	OUTSIDE	5349
LT. STA. 800+27 TO LT. STA. 825+76	OUTSIDE	2549
LT. STA. 800+27 TO LT. STA. 825+76	MEDIAN	2549
RT. STA. 800+27 TO RT. STA. 825+76	MEDIAN	2549
RT. STA. 800+27 TO RT. STA. 825+76	OUTSIDE	2549
TOTAL =		82,535

SHORT-TERM PAVEMENT MARKING				
LOCATION			MARKING LENGTH	TYPE
STA.	STA.	LT./RT.	FOOT	
I-72				
607+45	825+76	RT	218	YELLOW DIAGONAL
607+45	825+76	RT	2,184	WHITE SKIP DASH
607+45	825+76	RT	218	WHITE DIAGONAL
607+45	825+76	LT	218	WHITE DIAGONAL
607+45	825+76	LT	2,184	WHITE SKIP DASH
607+45	825+76	LT	218	YELLOW DIAGONAL
RAMP A				
100+00	118+19	RT	92	WHITE DIAGONAL
102+48	102+98	LT	100	2 - 50' SOLID WHITE
102+48	106+62	LT	44	WHITE SKIP DASH
106+62	118+19	LT	58	YELLOW DIAGONAL
RAMP B				
201+31	223+48	RT	112	WHITE DIAGONAL
201+31	212+98	LT	60	YELLOW DIAGONAL
212+98	217+92	LT	52	WHITE SKIP DASH
RAMP C				
300+00	319+68	RT	100	WHITE DIAGONAL
302+62	303+12	LT	100	2 - 50' SOLID WHITE
303+12	306+62	LT	36	WHITE SKIP DASH
306+62	319+68	LT	66	YELLOW DIAGONAL
RAMP D				
401+16	425+14	RT	120	WHITE DIAGONAL
401+16	414+65	LT	68	YELLOW DIAGONAL
414+65	419+21	LT	48	WHITE SKIP DASH
SUBTOTAL			6,296	
APPLICATIONS			3	
TOTAL			18,888	

PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5"				
LOCATION			MARKING LENGTH	TYPE
STA.	STA.	LT./RT.	FOOT	
607+45	797+09	RT	4750	WHITE SKIP DASH
607+45	797+09	LT	4750	WHITE SKIP DASH
801+27	825+76	LT	620	WHITE SKIP DASH
801+27	825+76	RT	620	WHITE SKIP DASH
TOTAL			10,740	

RAISED REFLECTIVE PAVEMENT MARKER				
LOCATION			NUMBER REQ'D	TYPE
STA.	STA.	LT./RT.	EACH	
I-72				
607+45	797+09	RT	239	ONE-WAY CRYSTAL
607+45	797+09	LT	239	ONE-WAY CRYSTAL
801+27	825+76	LT	63	ONE-WAY CRYSTAL
801+27	825+76	RT	63	ONE-WAY CRYSTAL
RAMP A				
100+00	106+62	RT	35	ONE-WAY CRYSTAL
102+48	106+62	LT	12	ONE-WAY CRYSTAL
106+62	112+05	LT	15	ONE-WAY AMBER
RAMP C				
300+00	306+62	RT	35	ONE-WAY CRYSTAL
302+62	306+62	LT	11	ONE-WAY CRYSTAL
306+62	312+26	LT	16	ONE-WAY AMBER
TOTAL			728	

PAVEMENT MARKING REMOVAL				
LOCATION			AREA	TYPE
STA.	STA.	LT./RT.	SQ FT	
I-72 (STAGE 1)				
795+00	804+00	LT	375	WHITE EDGE LINE
795+15	796+54	LT	15	WHITE SKIP DASH
801+82	804+00	LT	23	WHITE SKIP DASH
794+30	803+30	RT	375	WHITE EDGE LINE
794+49	796+54	RT	22	WHITE SKIP DASH
801+82	803+22	RT	15	WHITE SKIP DASH
I-72 (STAGE 2)				
795+15	796+54	LT	58	YELLOW EDGE LINE
801+82	803+87	LT	85	YELLOW EDGE LINE
794+43	796+54	RT	88	YELLOW EDGE LINE
801+82	803+22	RT	58	YELLOW EDGE LINE
FAS 630 (CH 33/DYE RD.) (STAGE 1)				
3341+50	3355+18	RT	570	WHITE EDGE LINE
3353+09	3355+18	RT	87	WHITE EDGE LINE
3353+54		RT	16	LEFT TURN ARROW
3355+06		RT	16	LEFT TURN ARROW
FAS 630 (CH 33/DYE RD.) (STAGE 2)				
3344+86	3356+00	LT	464	WHITE EDGE LINE
3344+86	3346+60	LT	73	WHITE EDGE LINE
3345+18		LT	16	LEFT TURN ARROW
3346+45		LT	16	LEFT TURN ARROW
TOTAL			2,370	

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL			
LOCATION			NUMBER REQ'D
STA.	STA.	LT./RT.	EACH
I-72			
607+45	797+09	RT	239
607+45	797+09	LT	239
801+27	825+76	LT	63
801+27	825+76	RT	63
RAMP A			
100+00	106+62	RT	35
102+48	106+62	LT	12
106+62	112+05	LT	15
RAMP C			
300+00	306+62	RT	35
302+62	306+62	LT	11
306+62	312+26	LT	16
TOTAL			728

HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH				
LOCATION	FOR INFO THICKNESS INCHES	LENGTH FOOT	WIDTH FOOT	SQ YD
I-72 (WB)				
LT. STA. 607+45 TO LT. STA. 608+00 (SHLD'S)	3.75 TO 1	55	16	97.8
LT. STA. 607+45 TO LT. STA. 608+00 (ML)	6 TO 3.25	55	24	146.7
LT. STA. 719+04.1 TO LT. STA. 723+53.1 (SHLD'S)	1 TO 2 5/8 TO 1.5	449	16	798.2
LT. STA. 720+04 TO LT. STA. 722+40 (ML)	3.25 TO 2.5	236	24	629.3
I-72 (EB)				
RT. STA. 607+45 TO RT. STA. 608+00 (SHLD'S)	3.75 TO 1	55	16	97.8
RT. STA. 607+45 TO RT. STA. 608+00 (ML)	6 TO 3.25	55	24	146.7
RT. STA. 719+04.1 TO RT. STA. 723+53.1 (SHLD'S)	1 TO 2 5/8 TO 1.5	449	16	798.2
RT. STA. 720+04 TO RT. STA. 722+40 (ML)	3.25 TO 2.5	236	24	629.3
FAI 72/FAS 630 (CH 33/DYE RD.) INTERCHANGE				
(RAMP A)				
STA. 106+62.4 TO STA. 107+07.4 (SHLD'S)	1 TO 1.5	45	10	50
(RAMP B)				
STA. 211+48 TO STA. 211+93 (SHLD'S)	1.5 TO 1	45	10	50
(RAMP C)				
STA. 306+62.4 TO STA. 307+07.4 (SHLD'S)	1 TO 1.5	45	10	50
(RAMP D)				
STA. 413+09.5 TO STA. 413+54.5 (SHLD'S)	1.5 TO 1	45	10	50
TOTAL =				3544

NOTE: TEMPORARY PAVEMENT MARKING QUANTITIES SAME AS PERMANENT PAVEMENT MARKING QUANTITIES.

TEMPORARY CONCRETE BARRIER

LOCATION	FOOT
STAGE I SN 084-0163(EB)/0164(WB)	
LT. STA. 797+02 TO LT. STA. 803+39	637.5
RT. STA. 794+97 TO RT. STA. 801+34	637.5
TOTAL =	1,275

RELOCATE TEMPORARY CONCRETE BARRIER

LOCATION	FOOT
STAGE II SN 084-0163(EB)/0164(WB)	
LT. STA. 797+02 TO LT. STA. 803+39	637.5
RT. STA. 794+97 TO RT. STA. 801+34	637.5
TOTAL =	1,275

BARRIER WALL MARKERS, TYPE C

LOCATION	EACH
STAGE I SN 084-0163(EB)/0164(WB)	
LT. STA. 797+02 TO LT. STA. 803+39	50
RT. STA. 794+97 TO RT. STA. 801+34	50
TOTAL =	100