

CLEANING UNDERDRAIN OUTLETS OUTLET MARKER		
USE 500' SPACING		
LOCATION	CLEAN EACH	MARKER EACH
I-72		
STA. 607+45 TO STA. 825+76	176	176
I-72/FAS 630 (CH 33/DYE RD.) INTERCHANGE (RAMP A)		
STA. 106+62 TO STA. 118+19	6	6
(RAMP B)		
STA. 201+31 TO STA. 212+68	6	6
(RAMP C)		
STA. 306+62 TO STA. 319+68	6	6
(RAMP D)		
STA. 401+16 TO STA. 414+65	6	6
TOTALS =	200	200

MATERIAL TRANSFER DEVICE

LOCATION	TON
I-72 BINDER COURSE SURFACE COURSE	28000 9883
TOTAL =	37,883

MAINTENANCE MOWING	
LOCATION	ACRE
I-72	
STA. 607+45 TO STA. 825+76	56
I-72/FAS 630 (CH 33/DYE RD.) INTERCHANGE (RAMP A)	
STA. 106+62 TO STA. 119+00	1
(RAMP B)	
STA. 201+00 TO STA. 211+50	1
(RAMP C)	
STA. 307+00 TO STA. 320+00	1
(RAMP D)	
STA. 401+00 TO STA. 413+00	1
	2 TIMES
TOTAL =	120

MODIFIED URETHANE PAVEMENT MARKING - LETTERS AND SYMBOLS		
LOCATION		SQ FT
FAS 630 (CH 33/DYE RD.)		
RT. STA. 3353+54	LEFT TURN ARROW	15.6
RT. STA. 3355+06	LEFT TURN ARROW	15.6
LT. STA. 3345+18	LEFT TURN ARROW	15.6
LT. STA. 3346+45	LEFT TURN ARROW	15.6
TOTAL =		63

MODIFIED URETHANE PAVEMENT MARKING - LINE 8'' GROOVING FOR RECESSED PAVEMENT MARKING 9''					
LOCATION			MARKING LENGTH	GROOVING	TYPE
STA.	STA.	LT./RT.	FOOT	FOOT	
RAMP A					
102+56	106+62	LT	812	812	(2 EACH OF SOLID WHITE)
100+00	102+56	LT	51	51	(12' SKIP, 3' DASH WHITE)
RAMP B	217+92	LT	988	988	(2 EACH OF SOLID WHITE)
212+98					
RAMP C	306+62	LT	798	798	(2 EACH OF SOLID WHITE)
302+63	302+63	LT	51	51	(12' SKIP, 3' DASH WHITE)
300+00					
RAMP D	419+21	LT	914	914	(2 EACH OF SOLID WHITE)
414+64					
TOTAL			3,614	3,614	

MODIFIED URETHANE PAVEMENT MARKING - LINE 12'' GROOVING FOR RECESSED PAVEMENT MARKING 13''					
LOCATION			MARKING LENGTH	GROOVING	TYPE
STA.	STA.	LT./RT.	FOOT	FOOT	
RAMP A					
102+56	106+62	LT	121	121	(CHEVRON SOLID WHITE)
RAMP C					
302+63	306+62	LT	114	114	(CHEVRON SOLID WHITE)
TOTAL			235	235	

TYPE C INLET BOX, STANDARD 609001 (SPECIAL)	
LOCATION	EACH
TR 546 (KENT FARM RD.)	
LT. STA. 4648+55	1
RT. STA. 4648+55	1
LT. STA. 4651+45	1
RT. STA. 4651+45	1
TOTAL =	4

TYPE E INLET BOX, STANDARD 610001 (SPECIAL)	
LOCATION	EACH
I-72	
LT. STA. 798+04 (INSIDE SHLD)	1
RT. STA. 798+04 (INSIDE SHLD)	1
TOTAL =	2

TYPE F INLET BOX, STANDARD 610001 (SPECIAL)	
LOCATION	EACH
I-72	
LT. STA. 798+04 (OUTSIDE SHLD)	1
RT. STA. 798+04 (OUTSIDE SHLD)	1
TOTAL =	2

MODIFIED URETHANE PAVEMENT MARKING - LINE 5'' GROOVING FOR RECESSED PAVEMENT MARKING 6''					
LOCATION			MARKING FOOT	GROOVING FOOT	TYPE
STA.	STA.	LT./RT.			
I-72					
607+45	825+76	RT	21831	21831	SOLID YELLOW
607+45	702+03	RT	9458	9458	SOLID WHITE
607+45	825+76	LT	21832	21832	SOLID YELLOW
607+45	699+58	LT	9213	9213	SOLID WHITE
708+66	734+11	RT	2545	2545	SOLID WHITE
710+08	732+42	LT	2234	2234	SOLID WHITE
739+04	825+76	LT	8672	8672	SOLID WHITE
744+61	825+76	RT	8115	8115	SOLID WHITE
797+09	801+27	LT	110	110	WHITE SKIP DASH
797+09	801+28	RT	110	110	WHITE SKIP DASH
I-72/FAS 630 (CH 33/DYE RD.) INTERCHANGE (RAMP A)					
100+00	118+19	RT	1819	1819	SOLID WHITE
106+62	118+19	LT	1157	1157	SOLID YELLOW
(RAMP B)					
201+31	212+98	LT	1167	1167	SOLID YELLOW
201+31	223+48	RT	2217	2217	SOLID WHITE
(RAMP C)					
300+00	319+68	RT	1968	1968	SOLID WHITE
306+62	319+68	LT	1306	1306	SOLID YELLOW
(RAMP D)					
401+16	414+64	LT	1348	1348	SOLID YELLOW
401+16	424+14	RT	2398	2398	SOLID WHITE
FAS 630 (CH 33/DYE RD.)					
3341+50	3355+18	RT	1368	1368	WHITE EDGE LINE
3344+82	3355+22		2080	2080	MEDIAN YELLOW EDGE LINE
3344+86	3356+00	LT	1114	1114	WHITE EDGE LINE
3344+86	3346+60	LT	174	174	WHITE EDGE LINE
3353+09	3355+18	RT	209	209	WHITE EDGE LINE
TOTALS			102,445	102,445	

IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3

LOCATION	EACH
STAGE I SN 084-0163(EB)/0164(WB)	
LT. STA. 803+47	1
RT. STA. 794+94	1
TOTAL =	2

IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3

LOCATION	EACH
STAGE II SN 084-0163(EB)/0164(WB)	
LT. STA. 803+42	1
RT. STA. 794+92	1
TOTAL =	2

BOX CULVERTS TO BE CLEANED

LOCATION	SIZE	FOOT
I-72		
STA. 777+00	TRIPLE 10.5'X8'	1050
TOTAL =		1,050