


I-72 CLASS A PATCHES, 8 INCH							
LOCATION	LANE	LENGTH (FOOT)	LANE WIDTH (FOOT)	CLASS A PATCH TYPE II (SQ. YD.)	CLASS A PATCH TYPE III (SQ. YD.)	SAWCUT (FOOT)	PATCHING REINFORCEMENT (SQ. YD.)
<b>WBL</b>							
709+00	DL	6	12	8		60	8
777+00	DL	10	12	13.3		68	13.3
779+50	DL	6	12	8		60	8
780+50	DL	6	12	8		60	8
782+00	DL	6	12	8		60	8
803+50	DL	6	12	8		60	8
805+00±	DL	6	12	8		60	8
806+00	DL	18	12		24	84	24
<b>EBL</b>							
538+10±	DL	6	12	8		60	8
555+00	DL	6	12	8		60	8
643+00	DL	10	12	13.3		68	13.3
703+00	DL	6	12	8		60	8
708+00	DL	6	12	8		60	8
708+50	DL	6	12	8		60	8
734+00	DL	16	12		21.3	80	21.3
736+00	DL	6	12	8		60	8
750+00	DL	6	12	8		60	8
750+10	DL	6	12	8		60	8
770+00	DL	6	12	8		60	8
777+00	DL	6	12	8		60	8
778+00	DL	6	12	8		60	8
780+00	DL	6	12	8		60	8
790+00	DL	10	12	13.3		68	13.3
794+00	DL	6	12	8		60	8
795+00	DL	6	12	8		60	8
810+00	DL	6	12	8		60	8
TOTAL =				207.9	45.3	1628	253.2
USE =				250	75	2085	325

PATCHING LOCATIONS SHOWN ARE APPROXIMATE.  
THE ACTUAL LOCATION SHALL BE SPECIFIED BY THE RESIDENT ENGINEER.

I-72/FAS 630 (CH 33/DYE RD.) RAMPS CL. B PATCHES 11 INCH							
LOCATION	LANE	LENGTH (FOOT)	LANE WIDTH (FOOT)	CLASS B PATCH TYPE II (SQ. YD.)		SAWCUT (FOOT)	DOWEL BARS 1 1/2 INCH (EACH)
<b>RAMP A</b>							
113+50	LT	6	8	5.3		36	14
	RT	6	8	5.3		36	14
<b>RAMP B</b>							
201+10	LT	6	8	5.3		36	14
	RT	6	8	5.3		36	14
213+00	LT	6	8	5.3		36	14
	RT	6	7	4.7		33	12
<b>RAMP C</b>							
313+50	LT	6	8	5.3		36	14
	RT	6	8	5.3		36	14
<b>RAMP D</b>							
402+50	LT	6	8	5.3		36	14
	RT	6	8	5.3		36	14
410+50	LT	6	8	5.3		36	14
	RT	6	8	5.3		36	14
TOTAL =				63		429	166
USE =				75		510	200

PATCHING LOCATIONS SHOWN ARE APPROXIMATE.  
THE ACTUAL LOCATION SHALL BE SPECIFIED BY THE RESIDENT ENGINEER.

FILE NAME = ... \CADD\1672C88-shr-schedule.dgn	USER NAME =	DESIGNED -	REVISED -
 Johnson, Depp & Olsenberry CONSULTING ENGINEERS Springfield, Illinois	PLOT SCALE = 100.0000' / 1in.	DRAWN -	REVISED -
	PLOT DATE = 04/03/2013 16:32:00	CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SCHEDULE OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
72	(84-10-3)RS-5	SANGAMON	95	45
CONTRACT NO. 72C88				
ILLINOIS FED. AID PROJECT				