



STA. 607+45 TO STA. 825+76.20
 STRUCTURE OMISSION
 STA. 797+09.00 TO STA. 801+27.00

LEGEND

- | | |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| <ul style="list-style-type: none"> ① EXISTING CRPCC PAVEMENT 8" ② EXISTING SRPCC PAVEMENT 8" ③ EXISTING HMA RESURFACING 3 1/4 " ④ NOT USED ⑤ EXISTING LONGITUDINAL JOINT ⑥ EXISTING STABILIZED SUBBASE 4" ⑦ EXISTING PIPE UNDERDRAIN ⑧ EXISTING HMA SHOULDER, 11 1/4 " ⑨ NOT USED ⑩ EXISTING AGGREGATE SHOULDER, TYPE A | <ul style="list-style-type: none"> ⑳ PROPOSED HOT-MIX ASPHALT SURFACE REMOVAL, 1" ㉑ PROPOSED HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2" ㉒ PROPOSED HOT-MIX ASPHALT SURFACE REMOVAL, 3 1/4" ㉓ NOT USED ㉔ PROPOSED POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90 (2 1/4") ㉕ PROPOSED POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90 (4 1/2") ㉖ PROPOSED POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90 (1 1/2") ㉗ NOT USED ㉘ PROPOSED HOT-MIX ASPHALT SHOULDERS (2") ㉙ PROPOSED HOT-MIX ASPHALT SHOULDERS (3 3/4") (W/RUMBLE STRIPS STD. 642001) ㉚ PROPOSED AGGREGATE SHOULDERS, TYPE B ㉛ PROPOSED MODIFIED URETHANE PAVEMENT MARKING - LINE 5" ㉜ PROPOSED PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 5" |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|

NOTES

1. MILL TO BARE CONCRETE AT INDICATED LOCATIONS.
2. NO PROPOSED RUMBLE STRIPS WILL BE PLACED ON RAMP SHOULDERS AT THE COUNTY HIGHWAY 33 INTERCHANGE.

FILE NAME =	USER NAME =	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TYPICAL SECTIONS FAI 72 (I-72)			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
... \CADD\1672C88-shit-typical.dgn		DRAWN -	REVISED -		72	(84-10-3)RS-5	SANGAMON	95	46			
	PLOT SCALE = 100.0000' / 1in.	CHECKED -	REVISED -		CONTRACT NO. 72C88							
	PLOT DATE = 04/02/2013 09:17:08	DATE -	REVISED -		ILLINOIS FED. AID PROJECT							
				SCALE:	SHEET NO.	OF	SHEETS	STA.	TO	STA.		