

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		URBAN 0005 M231	RURAL 0005 M232
20200600	EXCAVATING AND GRADING EXISTING SHOULDER	UNIT	1061	167	894
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	23	2	21
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	17381	3530	13851
40600300	AGGREGATE (PRIME COAT)	TON	348	71	277
40600635	LEVELING BINDER (MACHINE METHOD), N70	TON	7921	1580	6341
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	667	267	400
40600990	TEMPORARY RAMP	SO YD	121	54	67
40603315	HOT-MIX ASPHALT SURFACE COURSE, "C", N70	MIX TON	15839	3160	12679
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	291	75	216
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	15345	9500	5845
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SO YD	8		8
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	205		205

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE	
CODE NO	ITEM	UNIT		URBAN 0005 M231	RURAL 0005 M232
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	40		40
44201823	CLASS D PATCHES, TYPE I, 15 INCH	SO YD	4		4
44201827	CLASS D PATCHES, TYPE II, 15 INCH	SO YD	1451		1451
44201839	CLASS D PATCHES, TYPE II, 16 INCH	SO YD	1558	523	1035
44201843	CLASS D PATCHES, TYPE III, 16 INCH	SO YD	415	200	215
44201845	CLASS D PATCHES, TYPE IV, 16 INCH	SO YD	167	62	105
44201859	CLASS D PATCHES, TYPE I, 18 INCH	SO YD	4	4	
44201863	CLASS D PATCHES, TYPE II, 18 INCH	SO YD	51	35	16
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	4364	796	3568
66700205	PERMANENT SURVEY MARKERS, TYPE I	EACH	7		7
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	1	5
67100100	MOBILIZATION	L SUM	1	0.2	0.8
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	0.2	0.8

FILE NAME :	USER NAME : staffennk	DESIGNED -	REVISED -
c:\pwork\pvidot\staffennk\0249325\074511\shl-soa.dgn		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES			
SCALE: NA	SHEET 1 OF 3 SHEETS	STA.	TO STA.

F.A.P. RTE. 824	SECTION (19,20)RS-4	COUNTY COLES	TOTAL SHEETS 56	SHEET NO. 3
CONTRACT NO. 74511				
ILLINOIS FED. AID PROJECT				