

PAVEMENT MARKING SCHEDULE (Cont'd)	LENGTH	PAINT PAVEMENT MARKING - LINE 4" WHITE	PAINT PAVEMENT MARKING - LINE 4" YELLOW	THERMOPLASTIC PAVEMENT MARKING - LINE 4" WHITE	THERMOPLASTIC PAVEMENT MARKING - LINE 4" YELLOW	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	THERMOPLASTIC PAVEMENT MARKING - LINE 12" WHITE	THERMOPLASTIC PAVEMENT MARKING - LINE 12" YELLOW	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	TEMPORARY PAVEMENT MARKING - LINE 4" WHITE	TEMPORARY PAVEMENT MARKING - LINE 4" YELLOW	TEMPORARY PAVEMENT MARKING - LINE 6"	TEMPORARY PAVEMENT MARKING - LINE 8"	TEMPORARY PAVEMENT MARKING - LINE 12" WHITE	TEMPORARY PAVEMENT MARKING - LINE 12" YELLOW	TEMPORARY PAVEMENT MARKING - LINE 24"	TEMPORARY PAVEMENT MARKING - LETTERS & SYMBOLS	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER		
																							STATION TO STATION	FOOT
U. S. RTE 45 (RURAL)																								
119+56.36 TO 158+60.00	3,903.6	7,807.3	975.9	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	7,807.3	975.9	0.0	0.0	0.0	0.0	0.0	0.0	1,568.0	174.2	49.0	
158+60.00 TO 164+50.00	590.0	0.0	0.0	1,180.0	1,180.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	1,180.0	1,180.0	0.0	0.0	0.0	0.0	0.0	0.0	240.0	26.7	7.0	
164+50.00 TO 167+15.00	265.0	0.0	0.0	530.0	530.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	530.0	530.0	0.0	0.0	0.0	0.0	0.0	0.0	112.0	12.4	5.0	
167+15.00 TO 173+40.00	625.0	0.0	0.0	1,250.0	1,250.0	625.0	0.0	0.0	0.0	0.0	140.4	1,250.0	1,250.0	625.0	0.0	0.0	0.0	0.0	0.0	0.0	140.4	512.0	56.9	27.0
173+40.00 TO 175+78.50	238.5	0.0	0.0	477.0	954.0	238.5	0.0	0.0	0.0	36.0	46.8	477.0	954.0	238.5	0.0	0.0	36.0	0.0	0.0	0.0	46.8	288.0	32.0	18.0
175+78.50 TO 176+65.00	86.5	0.0	0.0	141.5	173.0	135.8	76.2	16.1	0.0	0.0	46.8	141.5	173.0	135.8	76.2	16.1	0.0	0.0	0.0	0.0	46.8	96.0	10.7	10.0
176+65.00 TO 177+80.00	115.0	0.0	0.0	46.3	0.0	0.0	218.9	107.6	0.0	44.3	0.0	46.3	0.0	0.0	218.9	107.6	0.0	44.3	0.0	0.0	0.0	0.0	4.0	
177+80.00 TO 180+45.00	265.0	0.0	0.0	524.5	530.0	265.0	0.0	0.0	0.0	0.0	78.0	524.5	530.0	265.0	0.0	0.0	0.0	0.0	0.0	78.0	224.0	24.9	21.0	
180+45.00 TO 184+00.00	355.0	0.0	0.0	710.0	1,420.0	0.0	0.0	0.0	0.0	103.0	0.0	710.0	1,420.0	0.0	0.0	0.0	103.0	0.0	0.0	0.0	288.0	32.0	19.0	
184+00.00 TO 189+00.00	500.0	0.0	0.0	1,000.0	1,000.0	0.0	0.0	0.0	0.0	0.0	0.0	1,000.0	1,000.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	208.0	23.1	9.0	
189+00.00 TO 380+80.00	19,180.0	37,705.0	4,795.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	37,705.0	4,795.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	7,680.0	853.3	240.0	
380+80.00 BK = 100+00.00 AH	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
100+00.00 TO 142+50.63	4,250.6	8,353.3	1,062.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	8,353.3	1,062.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	1,696.0	188.4	53.0	
142+50.63 TO 143+70.89	120.3	240.5	30.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	240.5	30.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
143+70.89 TO 223+74.50	8,003.6	15,281.2	2,000.9	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	15,281.2	2,000.9	0.0	0.0	0.0	0.0	0.0	0.0	0.0	3,200.0	355.6	100.0	
223+74.50 BK = 505+61.40 AH	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
505+61.40 TO 541+03.96	3,542.6	6,919.1	885.6	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	6,919.1	885.6	0.0	0.0	0.0	0.0	0.0	0.0	0.0	1,424.0	158.2	44.0	
541+03.96 TO 541+94.04	90.1	180.2	22.5	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	180.2	22.5	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	
541+94.04 TO 618+53.00	7,659.0	15,031.9	1,914.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	15,031.9	1,914.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	3,056.0	339.6	96.0	
RURAL TOTAL		91,518.0	11,687.0	5,859.0	7,037.0	1,264.0	295.0	124.0	139.0	44.0	312.0	97,378.0	18,724.0	1,264.0	295.0	124.0	139.0	44.0	312.0	20,592.0	2,288.0	702.0		
URBAN SHEET TOTAL		20,372.0	3,405.0	2,700.0	4,634.0	560.0	117.0	55.0	262.0	0.0	156.0	23,072.0	8,039.0	560.0	117.0	55.0	262.0	0.0	156.0	5,264.0	585.0	221.0		
PROJECT TOTALS		111,890.0	15,092.0	8,559.0	11,671.0	1,824.0	412.0	179.0	401.0	44.0	468.0	120,450.0	26,763.0	1,824.0	412.0	179.0	401.0	44.0	468.0	25,856.0	2,873.0	923.0		