

PAVEMENT MARKING SCHEDULE

STATION TO STATION	LENGTH	THERMOPLASTIC PAVEMENT MARKING - LINE 4" WHITE	THERMOPLASTIC PAVEMENT MARKING - LINE 4" YELLOW	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	THERMOPLASTIC PAVEMENT MARKING - LINE 12" WHITE	THERMOPLASTIC PAVEMENT MARKING - LINE 12" YELLOW	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	THERMOPLASTIC PAVEMENT MARKING - LETTERS & SYMBOLS	TEMPORARY PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 6"	TEMPORARY PAVEMENT MARKING - LINE 8"	TEMPORARY PAVEMENT MARKING - LINE 12"	TEMPORARY PAVEMENT MARKING - LINE 24"	TEMPORARY PAVEMENT MARKING - LETTERS & SYMBOLS	SHORT-TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER
	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	FOOT	SO FT	FOOT	FOOT	FOOT	FOOT	FOOT	SO FT	FOOT	SO FT	EACH
IL 130																		
803+40.50 TO 807+60.50	420.0	840.0	525.0	0.0	0.0	0.0	0.0	0.0	0.0	1365.0	0.0	0.0	0.0	0.0	0.0	176.0	14.7	5.0
807+60.50 TO 808+40.50	80.0	160.0	160.0	0.0	0.0	0.0	0.0	0.0	0.0	320.0	0.0	0.0	0.0	0.0	0.0	32.0	2.7	6.0
808+40.50 TO 814+05.50	565.0	1130.0	2260.0	0.0	0.0	122.3	0.0	0.0	0.0	3390.0	0.0	0.0	122.3	0.0	0.0	224.0	18.7	30.0
814+05.50 TO 816+70.50	265.0	349.0	530.0	265.0	0.0	0.0	0.0	0.0	62.4	879.0	265.0	0.0	0.0	0.0	62.4	224.0	18.7	21.0
816+70.50 TO 817+52.60	82.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	30.0
817+52.60 TO 820+17.60	265.0	410.0	530.0	530.0	0.0	0.0	0.0	0.0	124.8	940.0	530.0	0.0	0.0	0.0	124.8	336.0	28.0	28.0
820+17.60 TO 825+82.60	565.0	1130.0	2260.0	0.0	0.0	122.4	0.0	0.0	0.0	3390.0	0.0	0.0	122.4	0.0	0.0	224.0	18.7	0.0
825+82.60 TO 826+62.60	80.0	160.0	160.0	0.0	0.0	0.0	0.0	0.0	0.0	320.0	0.0	0.0	0.0	0.0	0.0	32.0	2.7	6.0
826+62.60 TO 830+82.60	420.0	840.0	525.0	0.0	0.0	0.0	0.0	0.0	0.0	1365.0	0.0	0.0	0.0	0.0	0.0	176.0	14.7	5.0
WEST SALEM ROAD																		
1017+49.00 TO 1018+39.80	90.8	181.6	22.7	0.0	0.0	0.0	0.0	0.0	0.0	204.3	0.0	0.0	0.0	0.0	0.0	32.0	2.7	2.0
1018+39.80 TO 1019+57.70	117.9	235.8	235.8	0.0	56.0	0.0	29.7	30.0	0.0	471.6	0.0	56.0	29.7	30.0	0.0	48.0	4.0	8.0
1019+57.70 TO 1019+73.00	15.3	30.6	0.0	0.0	91.2	0.0	61.6	0.0	0.0	30.6	0.0	91.2	61.6	0.0	0.0	0.0	0.0	0.0
1019+73.00 TO 1020+00.00	27.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	16.0	1.3	0.0
1020+00.00 BK = 0+00.00 AH	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
0+00.00 TO 0+09.00	9.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
0+09.00 TO 0+25.10	16.1	32.2	0.0	0.0	95.2	0.0	64.9	0.0	0.0	32.2	0.0	95.2	64.9	0.0	0.0	0.0	0.0	0.0
0+25.10 TO 1+83.00	157.9	315.8	315.8	0.0	60.2	0.0	36.7	29.0	0.0	631.6	0.0	60.2	36.7	29.0	0.0	64.0	5.3	10.0
TOTALS		5815.0	7524.0	795.0	303.0	245.0	193.0	59.0	187.0	13339.0	795.0	303.0	438.0	59.0	187.0	1584.0	132.0	151.0