


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	90% FED 10% STATE		100% STATE		CONSTRUCTION CODE											
				FAI 55 ROADWAY 0004 RURAL	STRUCTURE 0014 SN 060-0181	FAI 55 ROADWAY 0021 RURAL													
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	324	324															
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4															
78300100	PAVEMENT MARKING REMOVAL	SQ FT	29586	29586															
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	873	873															
80300100	LOCATING UNDERGROUND CABLE	FOOT	16215	16215															
X0323583	SPEED INDICATOR SIGN	CAL DA	230	230															
X0324743	SUBGRADE REINFORCEMENT	SQ YD	8667	8667															
X0325510	VIDEO TAPING OF PIPE UNDERDRAINS	FOOT	7300	7300															
+ * X0325667	WEED CONTROL MOWING STRIP (SPECIAL)	SQ YD	6666	6666															
X0326208	ALTERNATE ROUTE SIGNING	L SUM	1	1															
X0326677	REMOVE HIGH TENSION CABLE MEDIAN BARRIER	FOOT	14750	14750															
X0326687	REMOVE HIGH TENSION CABLE MEDIAN BARRIER TERMINAL	EACH	6	6															
X2020410	EARTH EXCAVATION (SPECIAL)	CU YD	20	20															
<del>X4400600</del>	<del>END SECTIONS TO BE REMOVED</del>	<del>EACH</del>	<del>2</del>	<del>2</del>															
X4401198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	77997	77997															

\* SPECIALTY ITEM  
+ NON-PARTICIPATING 100% STATE

FILE NAME *	USER NAME * #USER#	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
...CAD\0876D99-444-500.DGN		DRAWN -	REVISED -					55	60-1,2,RS-3	MADISON	212	13
 Johnson, Depp & Gulsenberry CONSULTING ENGINEERS Springfield, Illinois	PLOT SCALE * 28.8000 // IN.	CHECKED -	REVISED -		SCALE:	SHEET NO. 10 OF 12 SHEETS	STA.	TO STA.	CONTRACT NO. 76D99			
	PLOT DATE * 02/02/2012 17:28:54	DATE -	REVISED -		[ILLINOIS] FED. AID PROJECT							