

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE								
				90% FED 10% STATE		100% STATE						
				FAI 55 ROADWAY 0004 RURAL	STRUCTURE 0014 SN 060-0181	FAI 55 ROADWAY 0021 RURAL						
X4421000	PARTIAL DEPTH PATCHING	TON	504	504								
X4830030	PORTLAND CEMENT CONCRETE SHOULDERS 8" (SPECIAL)	SQ YD	6445	6445								
+ X5420624	PIPE CULVERTS TO BE CLEANED 24"	FOOT	690	690								
X5870015	BRIDGE DECK CONCRETE SEALER	SQ FT	9,665		9,665							
X6015000	REMOVE CONCRETE HEADWALLS FOR PIPE DRAINS	EACH	121	121								
X6350120	DELINEATOR REMOVAL	EACH	37	37								
X7270025	REMOVE EXISTING SIGN SUPPORT	EACH	36	36								
X8570000	SMART TRAFFIC MONITORING SYSTEM	L SUM	1	1								
+ Z0005305	BOX CULVERTS TO BE CLEANED	FOOT	325	325								
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	80	80								
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	40	40								
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1								
Z0016702	DETOUR SIGNING	L SUM	1	1								
+ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	21	21								
* Z0029652	HIGH TENSION CABLE MEDIAN BARRIER	FOOT	14650	14650								

* SPECIALTY ITEM
+ NON-PARTICIPATING 100% STATE