

(APPLY TO FINAL POLY. BINDER AND FINAL HMA SURFACE COURSE)

| SHORT TERM PAVEMENT MARKING | |
|--|--------|
| LOCATION | FOOT |
| I-55 | |
| SB (OUTSIDE) STA. 519+00 TO STA. 532+50 (WHITE) | 108 |
| SB (OUTSIDE) STA. 535+50 TO STA. 561+00 (WHITE) | 204 |
| SB (OUTSIDE) STA. 567+50 TO STA. 670+00 (WHITE) | 820 |
| SB (CENTERLINE) STA. 519+00 TO STA. 670+00 (WHITE SKIP DASH) | 2744 |
| SB (INSIDE) STA. 519+00 TO STA. 670+00 (YELLOW) | 1208 |
| | |
| NB (OUTSIDE) STA. 519+00 TO STA. 532+80 (WHITE) | 112 |
| NB (OUTSIDE) STA. 539+00 TO STA. 566+50 (WHITE) | 220 |
| NB (OUTSIDE) STA. 569+20 TO STA. 670+00 (WHITE) | 808 |
| NB (CENTERLINE) STA. 519+00 TO STA. 670+00 (WHITE SKIP DASH) | 2744 |
| NB (INSIDE) STA. 519+00 TO STA. 670+00 (YELLOW) | 1208 |
| | |
| IL 4 RAMPS | |
| RAMP 1 STA. 100+50 TO STA. 113+00 (YELLOW) | 100 |
| STA. 100+50 TO STA. 124+50 (WHITE) | 192 |
| RAMP 2 STA. 200+00 TO STA. 214+00 (WHITE) | 112 |
| STA. 207+00 TO STA. 214+00 (YELLOW) | 56 |
| RAMP 3 STA. 300+50 TO STA. 312+50 (YELLOW) | 96 |
| STA. 300+50 TO STA. 324+50 (WHITE) | 192 |
| RAMP 4 STA. 400+15 TO STA. 413+75 (WHITE) | 108 |
| STA. 407+00 TO STA. 413+75 (YELLOW) | 56 |
| TOTAL = | 11,088 |


| TEMPORARY PAVEMENT MARKING - LINE 4'' | |
|--|-------|
| LOCATION | FOOT |
| IL 4 RAMPS | |
| RAMP 1 | |
| STA. 101+25.10 TO STA. 112+56.16 (YELLOW EDGELINE) LT | 1131 |
| STA. 101+25.10 TO STA. 112+56.16 (WHITE EDGELINE) RT | 1131 |
| INTERSECTION WITH IL. RTE 4 (WHITE EDGELINE) RT | 166 |
| INTERSECTION WITH IL. RTE 4 (YELLOW EDGELINE) LT | 79 |
| RAMP 2 | |
| STA. 207+11.25 TO STA. 212+92.14 (YELLOW EDGELINE) LT | 581 |
| STA. 207+11.25 TO STA. 212+92.14 (WHITE EDGELINE) RT | 581 |
| INTERSECTION WITH IL. RTE 4 (WHITE EDGELINE) RT | 206 |
| INTERSECTION WITH IL. RTE 4 (YELLOW EDGELINE) LT | 140 |
| ISLAND AT INTERSECTION WITH IL. RTE. 4 (WHITE EDGELINE) | 31 |
| ISLAND AT INTERSECTION WITH IL. RTE. 4 (YELLOW EDGELINE) | 19 |
| RAMP 3 | |
| STA. 301+17.61 TO STA. 312+29.68 (YELLOW EDGELINE) LT | 1112 |
| STA. 301+17.61 TO STA. 312+29.68 (WHITE EDGELINE) RT | 1112 |
| INTERSECTION WITH IL. RTE 4 (WHITE EDGELINE) RT | 162 |
| INTERSECTION WITH IL. RTE 4 (YELLOW EDGELINE) LT | 77 |
| RAMP 4 | |
| STA. 407+32.69 TO STA. 412+60.17 (YELLOW EDGELINE) LT | 527 |
| STA. 407+32.69 TO STA. 412+60.17 (WHITE EDGELINE) RT | 527 |
| INTERSECTION WITH IL. RTE 4 (WHITE EDGELINE) RT | 218 |
| INTERSECTION WITH IL. RTE 4 (YELLOW EDGELINE) LT | 136 |
| ISLAND AT INTERSECTION WITH IL. RTE. 4 (WHITE EDGELINE) | 48 |
| ISLAND AT INTERSECTION WITH IL. RTE. 4 (YELLOW EDGELINE) | 31 |
| TOTAL = | 8,015 |

| TEMPORARY PAVEMENT MARKING - LINE 6'' | |
|--|--------|
| LOCATION | FOOT |
| I-55 | |
| STA. 519+00.00 TO STA. 670+00.00 (YELLOW EDGELINE) LT & RT | 30200 |
| STA. 519+00.00 TO STA. 670+00.00 (WHITE SKIP DASH) LT & RT | 7550 |
| STA. 519+00.00 TO STA. 532+82.32 (WHITE EDGELINE) LT | 1382 |
| STA. 519+00.00 TO STA. 532+48.89 (WHITE EDGELINE) RT | 1349 |
| STA. 539+68.00 TO STA. 555+69.64 (WHITE EDGELINE) RT | 1602 |
| STA. 544+42.25 TO STA. 562+04.57 (WHITE EDGELINE) LT | 1762 |
| STA. 567+41.54 TO STA. 670+00.00 (WHITE EDGELINE) RT | 10258 |
| STA. 569+15.97 TO STA. 670+00.00 (WHITE EDGELINE) LT | 10084 |
| | |
| IL 4 RAMPS | |
| RAMP 1 | |
| STA. 112+56.16 TO STA. 124+59.72 (WHITE EDGELINE) RT | 1204 |
| RAMP 2 | |
| STA. 200+00.21 TO STA. 207+11.25 (WHITE EDGELINE) RT | 711 |
| RAMP 3 | |
| STA. 312+29.68 TO STA. 324+50.13 (WHITE EDGELINE) RT | 1220 |
| RAMP 4 | |
| STA. 400+13.09 TO STA. 407+32.69 (WHITE EDGELINE) RT | 720 |
| TOTAL = | 68,042 |

| TEMPORARY PAVEMENT MARKING - LINE 8'' | |
|--|-------|
| LOCATION | FOOT |
| I-55 | |
| STA. 537+66.07 TO STA. 539+68.00 (WHITE EDGELINE) RT | 215 |
| STA. 542+15.33 TO STA. 544+42.25 (WHITE EDGELINE) LT | 233 |
| STA. 555+69.64 TO STA. 557+97.25 (WHITE EDGELINE) RT | 234 |
| STA. 562+04.57 TO STA. 563+84.59 (WHITE EDGELINE) LT | 193 |
| | |
| IL 4 RAMPS | |
| RAMP 1 | |
| STA. 112+56.16 TO STA. 115+28.59 (WHITE EDGELINE) LT | 272 |
| RAMP 2 | |
| STA. 205+32.07 TO STA. 207+11.25 (WHITE EDGELINE) LT | 179 |
| RAMP 3 | |
| STA. 312+29.68 TO STA. 315+03.56 (WHITE EDGELINE) LT | 274 |
| RAMP 4 | |
| STA. 405+30.92 TO STA. 407+32.69 (WHITE EDGELINE) LT | 202 |
| TOTAL = | 1,802 |

| TEMPORARY PAVEMENT MARKING - LINE 12'' | |
|--|-------|
| LOCATION | FOOT |
| IL 4 RAMPS | |
| RAMP 1 | |
| IL. RTE. 4 TO STA. 115+28.59 (WHITE EDGELINE) RT | 884 |
| RAMP 2 | |
| STA. 205+32.07 TO IL. RTE. 4 (WHITE EDGELINE) RT | 544 |
| RAMP 3 | |
| IL. RTE. 4 TO STA. 315+03.56 (WHITE EDGELINE) RT | 867 |
| RAMP 4 | |
| STA. 405+30.92 TO IL. RTE. 4 (WHITE EDGELINE) RT | 544 |
| TOTAL = | 2,839 |

| WORK ZONE PAVEMENT MARKING REMOVAL | |
|---|---------|
| LOCATION | SQ. FT. |
| SHORT-TERM PAVEMENT MARKING (ONLY SURFACE APPLICATION) | 1848 |
| TOTALS = | 1,848 |

| | | | |
|--|---------------------------------|------------|-----------|
| FILE NAME = | USER NAME = \$(USER) | DESIGNED - | REVISED - |
| ... \CADD\0876D99-Sht-Schedules.dgn | | DRAWN - | REVISED - |
|  Johnson, Depp & Quisenberry CONSULTING ENGINEERS Springfield, Illinois | PLOT SCALE = 100.0000' / IN. | CHECKED - | REVISED - |
| | PLOT DATE = 02/02/2012 17:28:32 | DATE - | REVISED - |

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

| | | | | |
|-------------|--------------|---------|---------------------------|-----------|
| F.A.I. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| 55 | 60-(1,2)RS-3 | MADISON | 212 | 29 |
| | | | CONTRACT NO. 76D99 | |
| | | | ILLINOIS FED. AID PROJECT | |