

TEMPORARY DITCH CHECKS	
LOCATION	FOOT
STA. 519+00	14
STA. 536+50	14
STA. 539+50	14
STA. 542+50	14
STA. 545+50	14
STA. 546+50	14
STA. 547+50	14
STA. 554+80	14
STA. 557+80	14
STA. 560+80	14
STA. 566+80	14
STA. 569+80	14
STA. 572+80	14
STA. 575+80	14
STA. 585+20	14
STA. 592+30	14
STA. 603+40	14
STA. 613+75	14
STA. 620+40	14
STA. 623+10	14
STA. 629+80	14
STA. 630+80	14
STA. 631+80	14
STA. 632+80	14
STA. 633+80	14
STA. 634+80	14
STA. 640+80	14
STA. 654+20	14
STA. 670+00	14
TOTAL =	406

SEEDING, CLASS 2	
LOCATION	ACRE
STA. 519+00 TO STA. 670+00	17.3
IL 4 RAMPS:	
RAMP 1 - STA. 100+27 TO STA. 113+10	0.6
RAMP 2 - STA. 207+00 TO STA. 214+28	0.3
RAMP 3 - STA. 300+26 TO STA. 312+70	0.6
RAMP 4 - STA. 406+90 TO STA. 413+95	0.3
TOTAL =	19.1
	(USE 19)

EROSION CONTROL BLANKET	
LOCATION	SQ. YD.
PIPE UNDERDRAIN OUTLETS	484
TOTAL =	484

NITROGEN FERTILIZER NUTRIENT		
LOCATION	ACRE	POUND
SEE SEEDING, CLASS 2	19	1,710
TOTAL =		1,710


INLET AND PIPE PROTECTION	
LOCATION	EACH
STA. 520+65	1
STA. 522+69	1
STA. 524+73	1
STA. 526+75	1
STA. 528+77	1
STA. 530+77	1
STA. 548+50	1
RT. STA. 562+28	1
RT. STA. 563+28	1
STA. 563+77	1
RT. STA. 580+08	1
STA. 580+20	1
STA. 603+34	1
STA. 611+40	1
STA. 617+75	1
STA. 617+91	1
STA. 635+77	1
STA. 644+69	1
STA. 661+23	1
IL 4 RAMPS:	
RT. STA. 110+10	1
RT. STA. 110+32	1
TOTAL =	21

PHOSPHORUS FERTILIZER NUTRIENT		
LOCATION	ACRE	POUND
SEE SEEDING, CLASS 2	19	1,710
TOTAL =		1,710

POTASSIUM FERTILIZER NUTRIENT		
LOCATION	ACRE	POUND
SEE SEEDING, CLASS 2	19	1,710
TOTAL =		1,710

MULCH, METHOD 2	
LOCATION	ACRE
STA. 519+00 TO STA. 670+00	17.3
IL 4 RAMPS:	
RAMP 1 - STA. 100+27 TO STA. 113+10	0.6
RAMP 2 - STA. 207+00 TO STA. 214+28	0.3
RAMP 3 - STA. 300+26 TO STA. 312+70	0.6
RAMP 4 - STA. 406+90 TO STA. 413+95	0.3
TOTAL =	19.1
	(USE 19)

TEMPORARY EROSION CONTROL SEEDING		
LOCATION	ACRE	POUND
SEE SEEDING, CLASS 2	19	1,900
TOTAL =		1,900

FILE NAME =	USER NAME = \$(USER)	DESIGNED -	REVISED -
... \CADD\0876D99-Shit-Erosion1.dgn		DRAWN -	REVISED -
 Johnson, Depp & Quisenberry CONSULTING ENGINEERS Springfield, Illinois	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -
	PLOT DATE = 02/02/2012 17:54:28	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULE OF EROSION CONTROL QUANTITIES			
SCALE:	SHEET NO.	OF SHEETS	STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	60-(1,2)RS-3	MADISON	212	63
				CONTRACT NO. 76D99
ILLINOIS FED. AID PROJECT				