

SIGNS SCHEDULE - BOND COUNTY

	SIGN TYPE	MUTCD/IL CODE	SIZE	AREA (SQ FT)	NO. OF SIGNS	SIGN PANEL TYPE 1 (SQ FT)	SIGN PANEL TYPE 2 (SQ FT)	WOOD SIGN SUPPORT (FOOT)	TELESCOPING STEEL SIGN SUPPORT (FOOT)	REM. SIGN PANEL ASSEMBLY	
										TYPE A (EACH)	TYPE B (EACH)
I-70 AND POKEY RD/470 E - DIAMOND INTERCHANGE											
EB/WB	WRONG WAY	R5-1A	42 X 30	8.75	4	35			56	5	
EB/WB	ONE WAY	R6-IL/R	54 X 18	6.75	8	54		56		3	
EB/WB	STOP	R1-1	36 X 36	9	4	36				4	
EB/WB	TURN PROHIBITION	R3-1	30 X 30	6.25	6	37.5		56			
EB/WB	DO NOT ENTER	R5-1	48 X 48	16	4		64	56			5
SUB-TOTAL						162.5	64	168	56	12	5
I-70 AND MILLERSBURG RD/970 E - PARTIAL CLOVERLEAF INTERCHANGE											
EB/WB	WRONG WAY	R5-1A	42 X 30	8.75	4	35			56	4	
EB/WB	ONE WAY	R6-IL/R	54 X 18	6.75	8	54		56		2	
EB/WB	STOP	R1-1	36 X 36	9	4	36				4	
EB/WB	ARROW SIGN	M6-2(GR)	30 X 18	3.75	2	7.5					
EB/WB	FREEWAY ENTRANCE	D13-3	48 X 30	10	2		20	28			
EB/WB	DO NOT ENTER	R5-1	48 X 48	16	6		96	56			4
EB/WB	KEEP RIGHT	R4-7	48 X 60	20	2		40	28			2
SUB-TOTAL						132.5	156	168	56	10	4
I-70 AND IL 127 - PARTIAL CLOVERLEAF INTERCHANGE											
EB/WB	WRONG WAY	R5-1A	42 X 30	8.75	4	35			56	4	
EB/WB	ONE WAY	R6-IL/R	54 X 18	6.75	8	54		56		2	
EB/WB	STOP	R1-1	36 X 36	9	4	18				4	
EB/WB	ARROW SIGN	M6-2(GR)	30 X 18	3.75	2	7.5					
EB/WB	FREEWAY ENTRANCE	D13-3	48 X 30	10	2		20	28			
EB/WB	DO NOT ENTER	R5-1	48 X 48	16	6		96	56			4
EB/WB	KEEP RIGHT	R4-7	48 X 60	20	2		40	28			2
SUB-TOTAL						132.5	156	168	56	10	6
I-70 AND MULBERRY GROVE RD - DIAMOND INTERCHANGE											
EB/WB	WRONG WAY	R5-1A	42 X 30	8.75	4	35			56	4	
EB/WB	ONE WAY	R6-IL/R	54 X 18	6.75	8	54		56		4	
EB/WB	STOP	R1-1	36 X 36	9	4	36				4	
EB/WB	TURN PROHIBITION	R3-1	30 X 30	6.25	6	37.5		56			
EB/WB	DO NOT ENTER	R5-1	48 X 48	16	4		64	56			4
SUB-TOTAL						162.5	64	168	56	12	4
TOTAL						590	440	672	224	44	19

PAVEMENT MARKINGS SCHEDULE - BOND COUNTY

DESCRIPTION		24" WHITE LINE (FT)	4" WHITE LINE (FT)	8" WHITE LINE (FT)	LETTERS AND SYMBOLS (SQ FT)	PAVEMENT MARKING REMOVAL (SQ FT)
STOP BAR	EB/WB	100				200
SINGLE LINE	EB/WB		500			166.7
THROUGH LANE-USE ARROW	EB/WB				22.9	22.9
TURN LANE-USE ARROW	EB/WB				62.4	62.4
TURN AND THROUGH LANE-USE ARROW	EB/WB				52	52
WRONG-WAY ARROW	EB/WB			73		
SUB-TOTAL		100	500	73	137.3	504.0
I-70 AND MILLERSBURG RD/970 E - PARTIAL CLOVERLEAF INTERCHANGE						
STOP BAR	EB/WB	91				182
SINGLE LINE	EB/WB		500			166.7
THROUGH LANE-USE ARROW	EB/WB				22.9	22.9
TURN LANE-USE ARROW	EB/WB				62.4	62.4
WRONG-WAY ARROW	EB/WB			73		
SUB-TOTAL		91	500	73	85.3	434.0
I-70 AND IL 127 - PARTIAL CLOVERLEAF INTERCHANGE						
STOP BAR	EB/WB	100				200
SINGLE LINE	EB/WB		500			166.7
THROUGH LANE-USE ARROW	EB/WB				22.9	22.9
TURN LANE-USE ARROW	EB/WB				62.4	62.4
WRONG-WAY ARROW	EB/WB			73		
SUB-TOTAL		100	500	73	85.3	452.0
I-70 AND MULBERRY GROVE RD - DIAMOND INTERCHANGE						
STOP BAR	EB/WB	89				178
SINGLE LINE	EB/WB		500			166.7
THROUGH LANE-USE ARROW	EB/WB				22.9	22.9
TURN LANE-USE ARROW	EB/WB				62.4	62.4
TURN AND THROUGH LANE-USE ARROW	EB/WB				52	52
WRONG-WAY ARROW	EB/WB			73		
SUB-TOTAL		89	500	73	137.3	482.0
TOTAL		380	2000	292	445.2	1872

FILE NAME =	USER NAME = gelnh	DESIGNED - _____	REVISED - _____
et:\pw_work\p\dot\gelnh\d0331963\0876034-sht-plan.dgn		DRAWN - _____	REVISED - _____
	PLOT SCALE = 100.0000' / in.	CHECKED - _____	REVISED - _____
#MODELNAME#	PLOT DATE = 3/28/2013	DATE - _____	REVISED - _____

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: _____ SHEET _____ OF _____ SHEETS STA. _____ TO STA. _____

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	DIST 8 WWD 2013-1	VARIOUS	24	6
CONTRACT NO. 76G34				
ILLINOIS FED. AID PROJECT				