

SIGNS SCHEDULE - MADISON COUNTY; CONT'D

SIGN TYPE	MUTCD/IL CODE	SIZE	AREA (SQ FT)	NO. OF SIGNS	SIGN PANEL TYPE 1 (SQ FT)	SIGN PANEL TYPE 2 (SQ FT)	WOOD SIGN SUPPORT (FOOT)	TELESCOPING STEEL SIGN SUPPORT (FOOT)	REM. SIGN PANEL ASSEMBLY		
									TYPE A (EACH)	TYPE B (EACH)	
IL 255 AND GATEWAY COMMERCE CENTER DR - DIAMOND INTERCHANGE											
NB/SB	WRONG WAY	R5-1A	42 X 30	8.75	4	35		56	4		
NB/SB	ONE WAY	R6-IL/R	54 X 18	6.75	8	54	56		4		
NB/SB	STOP	R1-1	36 X 36	9	4	36			4		
NB/SB	TURN PROHIBITION	R3-1 & 2	30 X 30	6.25	6	37.5	56				
NB/SB	DO NOT ENTER	R5-1	48 X 48	16	4		64	56		4	
NB/SB	KEEP RIGHT	R4-7 & 8	48 X 60	20	2		40	28		2	
SUB-TOTAL						162.5	104	196	56	12	6
I-255 AND IL 162 - PARTIAL CLOVERLEAF INTERCHANGE											
NB/SB	WRONG WAY	R5-1A	42 X 30	8.75	4	35		56	4		
NB/SB	ONE WAY	R6-IL/R	54 X 18	6.75	8	54	56		2		
NB/SB	STOP	R1-1	36 X 36	9	2	18			4		
NB/SB	ARROW SIGN	M6-2(GR)	30 X 18	3.75	2	7.5					
NB/SB	FREEWAY ENTRANCE	D13-3	48 X 30	10	2		20	28			
NB/SB	DO NOT ENTER	R5-1	48 X 48	16	6		96	56		4	
NB/SB	KEEP RIGHT	R4-7 & 8	48 X 60	20	2		40	28		2	
SUB-TOTAL						114.5	156	168	56	10	6
I-255 AND HORSESHOE LAKE RD - PARTIAL CLOVERLEAF INTERCHANGE											
NB/SB	WRONG WAY	R5-1A	42 X 30	8.75	4	35		56	4		
NB/SB	ONE WAY	R6-IL/R	54 X 18	6.75	8	54	56		1		
NB/SB	ARROW SIGN	M6-2(GR)	30 X 18	3.75	2	7.5					
NB/SB	FREEWAY ENTRANCE	D13-3	48 X 30	10	2		20	28			
NB/SB	DO NOT ENTER	R5-1	48 X 48	16	6		96	56		4	
NB/SB	KEEP RIGHT	R4-7 & 8	48 X 60	20	2		40	28		1	
SUB-TOTAL						96.5	156	168	56	5	5
I-270 AND IL 157/N BUFF RD - DIAMOND INTERCHANGE											
EB/WB	WRONG WAY	R5-1A	42 X 30	8.75	4	35		56	4		
EB/WB	ONE WAY	R6-IL/R	54 X 18	6.75	8	54	56		1		
EB/WB	STOP	R1-1	36 X 36	9	2	18			2		
EB/WB	TURN PROHIBITION	R3-1 & 2	30 X 30	6.25	6	37.5	56				
EB/WB	DO NOT ENTER	R5-1	48 X 48	16	4		64	56		4	
EB/WB	KEEP RIGHT	R4-7 & 8	48 X 60	20	2		40	28		2	
SUB-TOTAL						144.5	104	196	56	7	6
I-270 AND TROY RD - DIAMOND INTERCHANGE											
EB/WB	WRONG WAY	R5-1A	42 X 30	8.75	4	35		56	4		
EB/WB	ONE WAY	R6-IL/R	54 X 18	6.75	8	54	56		2		
EB/WB	TURN PROHIBITION	R3-1 & 2	30 X 30	6.25	6	37.5	56				
EB/WB	DO NOT ENTER	R5-1	48 X 48	16	4		64	56		4	
EB/WB	KEEP RIGHT	R4-7 & 8	48 X 60	20	2		40	28		2	
SUB-TOTAL						126.5	104	196	56	6	6
I-70 AND IL 4 - DIAMOND INTERCHANGE											
EB/WB	WRONG WAY	R5-1A	42 X 30	8.75	4	35		56	4		
EB/WB	ONE WAY	R6-IL/R	54 X 18	6.75	8	54	56		4		
EB/WB	STOP	R1-1	36 X 36	9	4	36			4		
EB/WB	TURN PROHIBITION	R3-1 & 2	30 X 30	6.25	6	37.5	56				
EB/WB	DO NOT ENTER	R5-1	48 X 48	16	4		64	56		4	
SUB-TOTAL						162.5	64	168	56	12	4

PAVEMENT MARKINGS SCHEDULE - MADISON COUNTY; CONT'D

DESCRIPTION		24" WHITE LINE (FT)	4" WHITE LINE (FT)	8" WHITE LINE (FT)	LETTERS AND SYMBOLS (SQ FT)	PAVEMENT MARKING REMOVAL (SQ FT)
STOP BAR	NB/SB	74				148
SINGLE LINE	NB/SB		500			166.7
THROUGH LANE-USE ARROW	NB/SB				91.6	91.6
TURN LANE-USE ARROW	NB/SB				124.8	124.8
WRONG-WAY ARROW	NB/SB			73		
SUB-TOTAL		74	500	73	216.4	531.1
I-255 AND IL 162 - PARTIAL CLOVERLEAF INTERCHANGE						
STOP BAR	NB/SB	62				124
SINGLE LINE	NB/SB		500			166.7
THROUGH LANE-USE ARROW	NB/SB				22.9	22.9
TURN LANE-USE ARROW	NB/SB				93.6	93.6
TURN AND THROUGH LANE-USE ARROW	NB/SB				52	52
WRONG-WAY ARROW	NB/SB			73		
SUB-TOTAL		62	500	73	168.5	459.2
I-255 AND HORSESHOE LAKE RD - PARTIAL CLOVERLEAF INTERCHANGE						
STOP BAR	NB/SB	189				378
SINGLE LINE	NB/SB		500			166.7
THROUGH LANE-USE ARROW	NB/SB				34.35	34.35
TURN LANE-USE ARROW	NB/SB				109.2	109.2
TURN AND THROUGH LANE-USE ARROW	NB/SB				26	26
WRONG-WAY ARROW	NB/SB			73		
SUB-TOTAL		189	500	73	169.55	714.2
I-270 AND IL 157/N BUFF RD - DIAMOND INTERCHANGE						
STOP BAR	EB/WB	231				462
SINGLE LINE	EB/WB		500			166.7
THROUGH LANE-USE ARROW	EB/WB				57.25	57.25
TURN LANE-USE ARROW	EB/WB				156	156
TURN AND THROUGH LANE-USE ARROW	EB/WB				26	26
WRONG-WAY ARROW	EB/WB			73		
SUB-TOTAL		231	500	73	239.25	867.9
I-270 AND TROY RD - DIAMOND INTERCHANGE						
STOP BAR	EB/WB	269				538
SINGLE LINE	EB/WB		500			166.7
THROUGH LANE-USE ARROW	EB/WB				91.6	91.6
TURN LANE-USE ARROW	EB/WB				124.8	124.8
WRONG-WAY ARROW	EB/WB			73		
SUB-TOTAL		269	500	73	216.4	921.1
I-70 AND IL 4 - DIAMOND INTERCHANGE						
STOP BAR	EB/WB	82				164
SINGLE LINE	EB/WB		500			166.7
TURN LANE-USE ARROW	EB/WB				62.4	62.4
TURN AND THROUGH LANE-USE ARROW	EB/WB				104	104
WRONG-WAY ARROW	EB/WB			73		
SUB-TOTAL		82	500	73	166.4	497.1

\*PERFORMED PLASTIC PVMT MKG, TYPE B

FILE NAME =	USER NAME = gelnh	DESIGNED - _____	REVISED - _____
et:\pw\work\p\d0331963\0876034-sht-plan.dgn		DRAWN - _____	REVISED - _____
#MODELNAME#	PLOT SCALE = 100.0000' / in.	CHECKED - _____	REVISED - _____
	PLOT DATE = 3/28/2013	DATE - _____	REVISED - _____

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

SCALE: \_\_\_\_\_ SHEET \_\_\_\_ OF \_\_\_\_ SHEETS STA. \_\_\_\_\_ TO STA. \_\_\_\_\_

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	DIST 8 WWD 2013-1	VARIOUS	24	10
CONTRACT NO. 76G34				
ILLINOIS FED. AID PROJECT				