CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE 80% FEDERAL, 20% STATE ROADWAY 0004 URBAN	TRAFFIC SIGNALS 0021 URBAN
44201377	CLASS C PATCHES, TYPE II, 12 INCH	SQ YD	102	102	
44201381	CLASS C PATCHES, TYPE III, 12 INCH	SQ YD	52	52	
44201383	CLASS C PATCHES, TYPE IV, 12 INCH	SQ YD	94	94	
48301000	PROTECTIVE COAT	SQ YD	6377	6377	
50300225	CONCRETE STRUCTURES	CU YD	2.34	2.34	
54248510	CONCRETE COLLAR	CU YD	1.1	1.1	
55100500	STORM SEWER REMOVAL 12"	FOOT	32	32	
55100700	STORM SEWER REMOVAL 15"	FOOT	57	57	
55100900	STORM SEWER REMOVAL 18"	FOOT	7	7	
55101200	STORM SEWER REMOVAL 24"	FOOT	598	598	
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	
60219500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 15 FRAME AND LID	EACH	1	1	
60224030	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 15 FRAME AND LID	EACH	1	1	
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	4	4	

14