

REMOVAL SCHEDULE

LOCATION STATION TO STATION	HOT-MIX ASPHALT SURFACE REMOVAL 3 1/4" (SQ YD)	PCC PAVEMENT REMOVAL (SQ YD)	SIDEWALK REMOVAL (SQ FT)	DRIVEWAY PAVEMENT REMOVAL (SQ YD)	STORM SEWER REMOVAL 12" (FOOT)	STORM SEWER REMOVAL 15" (FOOT)	STORM SEWER REMOVAL 18" (FOOT)	STORM SEWER REMOVAL 24" (FOOT)	REMOVING MANHOLES (EACH)	REMOVING INLETS (EACH)	COMBINATION CURB AND GUTTER REMOVAL (FOOT)	REMOVAL OF POLE FOUNDATION (EACH)	TRENCH BACKFILL (CU YD)
IL 37													
50+90.08 TO 52+98.00	1307												
51+05.84, 32.04 LT. TO 51+37.43, 32.56 LT.					32								
51+32.00 TO 52+98.00											422		
51+37.67 RT.										1			5
51+39.00 TO 53+55.00			1061										
51+39.18 LT.										1			5
51+40.87 TO 57+48.74							598						
51+85.00 RT. TO 53+92.00 RT.				176									
52+66.00 LT TO 0+50 NE RAD.				256									
52+79.09 LT.									1				5
52+98.00 TO 56+02.00 & 735+00.00 TO 737+77.00	3360												
52+98.00 RT. TO 735+00.00 LT.											268		
53+06.63 LT.									1				5
53+90 TO 54+15			561										
54+05.75 LT.										1			5
54+06.64, 40.95 LT. TO 54+10.63, 34.51 LT.						8							
54+11.55 LT.									1				5
54+18.44 LT.									1				5
54+77.57 LT.									1				5
54+84.30 LT.									1				5
54+85.16, 36.18 LT. TO 54+88.68, 42.43 LT.							7						
54+86 LT. TO 55+08 LT.			197										
54+89.45 LT.										1			5
55+25.00 TO 57+63.00			1327										
56+02.00 TO 57+63.00											417		
56+02.00 RT. TO 737+82.19 RT.											398		
56+02.00 TO 58+06.29	1299												
56+90.00 RT. TO 57+33.00 RT.				58									
IL 149													
732+37.79 TO 735+00.00	1650												
732+72 LT. TO 735+67.00 LT.				148									
732+73.00 TO 735+00.00											252		
732+73.00 TO 735+50.00			1643										
732+78.45 RT.										1			5
732+91.51 RT.												1	
733+46.00 RT. TO 734+36.00 RT.				130									
733+55.65 LT.												1	
733+95.98 RT.												1	
734+74.78 LT.												1	
735+00.00 RT. TO 56+02.00 RT.											208		
735+23.91 RT.												1	
735+50.00 RT. TO 55+25.00 RT.			508										
735+78.56 LT.												1	
736+61.45, 36.14 RT. TO 737+10.73, 31.83 RT.						49							
736+78.23 LT.												1	
736+96.00 TO 737+77.00			1058										
737+07.44 RT.												1	
737+77.00 LT. TO 52+98.00 LT.											307		
0+50 NE RAD. TO 737+81.00 LT				157									
0+75.00 SE RAD. TO 57+49.00 LT.				674									
TOTALS	4256	3360	6355	1599	32	57	7	598	6	5	2272	8	55

FILE NAME =	USER NAME = naosdp	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES (REMOVALS)	SCALE:	SHEET NO.	OF	SHEETS	STA.	TO STA.	F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
es:\pw\work\p\midot\naosdp\d0293206\78288-sh-t-plan.dgn		DRAWN -	REVISED -			9481	12(N-1)	FRANKLIN	94	16				CONTRACT NO. 78288		
PLOT SCALE = 100.0000' / in.		CHECKED -	REVISED -									ILLINOIS FED. AID PROJECT				
PLOT DATE = 3/22/2013		DATE -	REVISED -													