

HSIP

F

SUMMARY OF QUANTITIES CONT.

COUNTY:	FRANKLIN	FRANKLIN
FUNDING:	90% FED 10% STATE	80% FED 20% STATE
LOCATION:	RURAL	RURAL
ROUTE:	FAS 2882 IL 37	FAS 2882 IL 37
TOTAL QUANTITY	ROADWAY 0004	STRUCTURE 0014

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	ROADWAY 0004	STRUCTURE 0014
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	4061	4061	
28000305	TEMPORARY DITCH CHECKS	FOOT	963	963	
28000400	PERIMETER EROSION BARRIER	FOOT	7835	7835	
28000500	INLET AND PIPE PROTECTION	EACH	17	17	
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	100	100	
35100100	AGGREGATE BASE COURSE, TYPE A	TON	279	279	
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	640	640	
40600300	AGGREGATE (PRIME COAT)	TON	56	56	
40600909	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-9.5FG, N90	TON	1863	1863	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	48	48	
40600990	TEMPORARY RAMP	SQ YD	25	25	
40603243	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, FG, N90	TON	917	917	
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	3456	3349	107
40800010	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	6999	6999	