BINDER THICKNESS SCHEDULE

STATION	Left Slope	Right Slope	CONTROL POINT	TOTAL HMA THICKNESS (IN)			BINDER COURSE (IL 19.0 FG) THICKNESS (IN)		
	%	%		LT	CTR	RT	LT	CTR	RT
197+00.00	-1.5%	-1.5%	CL	2.99	2.25	3.15	RESURFACE	RESURFACE	RESURFACE
197+50.00	-1.5%	-1.5%	CL	2.90	2.25	3.16	RESURFACE	RESURFACE	RESURFACE
198+00.00	-1.5%	-1.5%	CL	2.82	2.25	3.17	RESURFACE	RESURFACE	RESURFACE
198+50.00	-1.5%	-1.5%	CL	3.09	2.25	2.75	RESURFACE	RESURFACE	RESURFACE
199+00.00	-1.5%	-1.5%	CL	3.36	2.25	2.27	1.11	RESURFACE	RESURFACE
199+50.00	-1.5%	-1.5%	CL	3.20	2.25	2.46	RESURFACE	RESURFACE	RESURFACE
200+00.00	-1.5%	-1.5%	CL	3.03	2.25	2.64	RESURFACE	RESURFACE	RESURFACE
200+50.00	-1.5%	-1.5%	CL	3.13	2.25	2.79	RESURFACE	RESURFACE	RESURFACE
201+00.00	-1.5%	-1.5%	CL	3.23	2.25	2.92	RESURFACE	RESURFACE	RESURFACE
201+50.00	-1.5%	-1.5%	CL	3.16	2.25	2.67	RESURFACE	RESURFACE	RESURFACE
202+00.00	-1.5%	-1.5%	CL	3.09	2.25	2.42	RESURFACE	RESURFACE	RESURFACE
202+50.00	-1.5%	-1.5%	CL	2.95	2.25	2.50	RESURFACE	RESURFACE	RESURFACE
203+00.00	-1.5%	-1.5%	CL	2.82	2.25	2.60	RESURFACE	RESURFACE	RESURFACE
203+50.00	-1.5%	-1.5%	CL	3.08	2.25	2.72	RESURFACE	RESURFACE	RESURFACE
204+00.00	-1.5%	-1.5%	CL	3.34	2.25	2.87	1.09	RESURFACE	RESURFACE
204+50.00	-1.5%	-1.5%	CL	3.24	2.25	2.99	RESURFACE	RESURFACE	RESURFACE
205+00.00	-1.5%	-1.5%	CL	3.09	2.25	3.45	RESURFACE	RESURFACE	1.20
205+50.00	-1.5%	-1.5%	CL	2.73	2.25	3.04	RESURFACE	RESURFACE	RESURFACE
206+00.00	-1.5%	-1.5%	CL	2.44	2.25	3.04	RESURFACE	RESURFACE	RESURFACE
206+50.00	-1.5%	-1.5%	CL	2.61	2.25	3.13	RESURFACE	RESURFACE	RESURFACE
207+00.00	-1.5%	-1.5%	CL	2.76	2.25	3.19	RESURFACE	RESURFACE	RESURFACE
207+50.00	-1.5%	-1.5%	CL	3.06	2.25	2.79	RESURFACE	RESURFACE	RESURFACE
208+00.00	-1.5%	-1.5%	CL	3.35	2.25	2.44	1.10	RESURFACE	RESURFACE
208+50.00	-1.5%	-1.5%	CL	2.86	2.25	2.52	RESURFACE	RESURFACE	RESURFACE
209+00.00	-1.5%	-1.5%	CL	2.38	2.25	2.68	RESURFACE	RESURFACE	RESURFACE
209+50.00	-1.5%	-1.5%	CL	2.80	2.25	3.08	RESURFACE	RESURFACE	RESURFACE
210+00.00	-1.5%	-1.5%	CL	3.25	2.25	3.48	1.00	RESURFACE	1.23
210+50.00	-1.5%	-1.5%	CL	3.00	2.25	3.20	RESURFACE	RESURFACE	RESURFACE
211+00.00	-1.5%	-1.5%	CL	2.76	2.25	2.93	RESURFACE	RESURFACE	RESURFACE
211+50.00	-1.5%	-1.5%	CL	2.93	2.25	3.16	RESURFACE	RESURFACE	RESURFACE
212+00.00	-1.5%	-1.5%	CL	3.08	2.25	3.35	RESURFACE	RESURFACE	1.10
212+50.00	-1.5%	-1.5%	CL	2.98	2.25	3.11	RESURFACE	RESURFACE	RESURFACE
213+00.00	-1.5%	-1.5%	CL	2.87	2.25	2.86	RESURFACE	RESURFACE	RESURFACE
213+50.00	-1.5%	-1.5%	CL	2.91	2.25	2.91	RESURFACE	RESURFACE	RESURFACE
214+00.00	-1.5%	-1.5%	CL	2.95	2.25	2.94	RESURFACE	RESURFACE	RESURFACE
214+50.00	-1.5%	-1.5%	CL	2.96	2.25	2.83	RESURFACE	RESURFACE	RESURFACE
215+00.00	-1.5%	-1.5%	CL	2.93	2.25	2.72	RESURFACE	RESURFACE	RESURFACE
215+50.00	-1.5%	-1.5%	CL	2.89	2.25	2.81	RESURFACE	RESURFACE	RESURFACE
216+00.00	-1.5%	-1.5%	CL	2.86	2.25	2.87	RESURFACE	RESURFACE	RESURFACE