BINDER THICKNESS SCHEDULE

STATION	Left Slope	Right Slope	CONTROL POINT	TOTAL HMA THICKNESS (IN)			BINDER COURSE (IL 19.0 FG) THICKNESS (IN)		
	%	%		LT	CTR	RT	LT	CTR	RT
236+00.00	-1.5%	-1.5%	CL	2.86	2.25	2.33	RESURFACE	RESURFACE	RESURFACE
236+50.00	-1.5%	-1.5%	CL	2.61	2.25	2.25	RESURFACE	RESURFACE	RESURFACE
237+00.00	-1.5%	-1.5%	RT	2.44	2.32	2.25	RESURFACE	RESURFACE	RESURFACE
237+50.00	-1.5%	-1.5%	CL	2.44	2.25	2.42	RESURFACE	RESURFACE	RESURFACE
238+00.00	-1.5%	-1.5%	CL	2.50	2.25	2.65	RESURFACE	RESURFACE	RESURFACE
238+50.00	-1.5%	-1.5%	CL	2.36	2.25	2.37	RESURFACE	RESURFACE	RESURFACE
239+00.00	-1.5%	-1.5%	RT	2.39	2.44	2.25	RESURFACE	RESURFACE	RESURFACE
239+50.00	-1.5%	-1.5%	RT	2.33	2.33	2.25	RESURFACE	RESURFACE	RESURFACE
240+00.00	-1.5%	-1.5%	CL	2.32	2.25	2.29	RESURFACE	RESURFACE	RESURFACE
240+50.00	-1.5%	-1.5%	LT	2.25	2.32	2.38	RESURFACE	RESURFACE	RESURFACE
241+00.00	-1.5%	-1.5%	LT	2.25	2.48	2.53	RESURFACE	RESURFACE	RESURFACE
241+50.00	-1.5%	-1.5%	LT	2.25	2.45	2.59	RESURFACE	RESURFACE	RESURFACE
242+00.00	-1.5%	-1.5%	LT	2.25	2.42	2.64	RESURFACE	RESURFACE	RESURFACE
242+50.00	-1.5%	-1.5%	LT	2.25	2.45	2.57	RESURFACE	RESURFACE	RESURFACE
243+00.00	-1.5%	-1.5%	LT	2.25	2.48	2.48	RESURFACE	RESURFACE	RESURFACE
243+50.00	-1.5%	-1.5%	LT	2.25	2.42	2.42	RESURFACE	RESURFACE	RESURFACE
244+00.00	-1.5%	-1.5%	LT	2.25	2.36	2.37	RESURFACE	RESURFACE	RESURFACE
244+50.00	-1.5%	-1.5%	LT	2.25	2.34	2.51	RESURFACE	RESURFACE	RESURFACE
245+00.00	-1.5%	-1.5%	LT	2.25	2.86	3.20	RESURFACE	RESURFACE	RESURFACE
245+50.00	-1.5%	-1.5%	LT	2.25	2.71	3.04	RESURFACE	RESURFACE	RESURFACE
246+00.00	-1.5%	-1.5%	LT	2.25	2.97	3.37	RESURFACE	RESURFACE	1.12
246+50.00	-1.5%	-1.5%	LT	2.25	2.79	3.27	RESURFACE	RESURFACE	1.02
247+00.00	-1.5%	-1.5%	LT	2.25	2.64	3.16	RESURFACE	RESURFACE	RESURFACE
247+50.00	-1.5%	-1.5%	LT	2.25	2.57	3.01	RESURFACE	RESURFACE	RESURFACE
248+00.00	-1.5%	-1.5%	LT	2.25	2.52	2.89	RESURFACE	RESURFACE	RESURFACE
248+50.00	-1.5%	-1.5%	LT	2.25	2.38	2.68	RESURFACE	RESURFACE	RESURFACE
249+00.00	-1.5%	-1.5%	CL	2.28	2.25	2.49	RESURFACE	RESURFACE	RESURFACE
249+50.00	-1.5%	-1.5%	LT	2.25	2.32	2.47	RESURFACE	RESURFACE	RESURFACE
250+00.00	-1.5%	-1.5%	LT	2.25	2.44	2.50	RESURFACE	RESURFACE	RESURFACE
250+50.00	-1.5%	-1.5%	LT	2.25	2.50	2.39	RESURFACE	RESURFACE	RESURFACE
251+50.00	-1.5%	-1.5%	RT	2.33	2.71	2.25	RESURFACE	RESURFACE	RESURFACE
252+00.00	-1.5%	-1.5%	RT	2.45	2.92	2.25	RESURFACE	RESURFACE	RESURFACE
252+50.00	-1.5%	-1.5%	RT	2.39	2.83	2.25	RESURFACE	RESURFACE	RESURFACE
253+00.00	-1.5%	-1.5%	RT	2.28	2.74	2.25	RESURFACE	RESURFACE	RESURFACE
253+50.00	-1.5%	-1.5%	LT	2.25	2.63	2.31	RESURFACE	RESURFACE	RESURFACE
254+00.00	-1.5%	-1.5%	CL	2.72	2.25	2.97	RESURFACE	RESURFACE	RESURFACE
254+50.00	-1.5%	-1.5%	CL	2.73	2.25	2.78	RESURFACE	RESURFACE	RESURFACE
255+00.00	-1.5%	-1.5%	CL	2.79	2.25	2.60	RESURFACE	RESURFACE	RESURFACE
255+50.00	-1.5%	-1.5%	CL	2.74	2.25	2.27	RESURFACE	RESURFACE	RESURFACE