EARTHWORK SCHEDULE

BAL	LOCATION STATION TO STATION	EARTH EXCAVATION	FOR INFORMATION ONLY					BORROW EXCAVATION	NOTES
			AVERAGE SHRINKAGE FACTOR	EARTH EXCAVATION (ADJUSTED)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)	BORROW PIT SHRINKAGE FACTOR		
		CU YD	%	CU YD	CU YD	CU YD	%	CU YD	
1	130+00 TO 183+00	8,137	29.6	5726	2,980	2,746			
2	183+00 TO 236+00	6,383	28.0	4598	3,236	1,362			
3	236+00 TO 19+00	654	24.8	492	4,229	-3,737	25%	4,983	USED 2,746 CU YD FROM BAL 1 & 1,362 CU YD FROM BAL 2
	IMPROVEMENT TOTALS:	15,174		10,816	10,446	371		875	

PAVEMENT MARKING SCHEDULE

STATION TO STATION				WET REFLECTIVE THERMOPLASTIC PAVEMENT MARKING - LINE 4"		TEMPORARY	SHORT-TERM	NOTES
				4 INCH WHITE (EDGELINE)	4 INCH (SKIP-DASH)	4 INCH	4 INCH	
IL 37 (FAS 2882/FAU 9481) - STA 129+86 TO STA 18+38								
	129+86.00	TO	187+54.40	11537	1,442	12979	3461	
EQ. STA187+54.4(BK) = STA 187+73.15(AH)								
	187+73.15	TO	253+63.61	13181	1,648	14829	3954	
BRIDGE	253+63.61	TO	257+70.19	813	102	915	244	
	257+70.19	TO	268+76.51	2213	277	2489	664	
EQ. STA 268+76.51 (BK) = STA 0+09.23 (AH)								
	+09.23	TO	18+38.00	3658	457	4115	1097	
SUB-TOTALS MAINLINE				31,401	3,925	35,326	9,421	