

SUMMARY OF QUANTITIES			
PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	184
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	140
20200100	EARTH EXCAVATION	CU YD	35711
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	3131
20400800	FURNISHED EXCAVATION	CU YD	4640
20700220	POROUS GRANULAR EMBANKMENT	CU YD	1882
20800150	TRENCH BACKFILL	CU YD	600
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	55053
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	5200
25000100	SEEDING, CLASS 1	ACRE	0.75
25000200	SEEDING, CLASS 2	ACRE	23.5
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	2179
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	2179
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	2179
25100115	MULCH, METHOD 2	ACRE	96.9
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	4072
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	7266
28000305	TEMPORARY DITCH CHECKS	FOOT	8078
28000400	PERIMETER EROSION BARRIER	FOOT	21950
28000500	INLET AND PIPE PROTECTION	EACH	46
28100105	STONE RIPRAP, CLASS A3	SQ YD	2064
28100107	STONE RIPRAP, CLASS A4	SQ YD	884
28200200	FILTER FABRIC	SQ YD	2949
31101100	SUBBASE GRANULAR MATERIAL, TYPE B	CU YD	2756
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	44067
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	5581
35101350	AGGREGATE BASE COURSE, TYPE A 15"	SQ YD	733
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	8236
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2203
40600115	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	GALLON	373
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	91
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	620
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	362
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	456
42000201	PORTLAND CEMENT CONCRETE PAVEMENT 7" (JOINTED)	SQ YD	42668

FILE NAME =  
#FILE#

USER NAME = #USER#  
PLOT SCALE = #SCALE#  
PLOT DATE = #DATE#

DESIGNED -  
DRAWN -  
CHECKED -  
DATE - MARCH 2013

REVISED -  
REVISED -  
REVISED -  
REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET NO. 3 OF 174 SHEETS STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
393	12-00001-01-RS	KNOX	174	3
COUNTY HIGHWAY #4		CONTRACT NO. 89614		
FED. ROAD DIST. NO. 4 [ILLINOIS] FED. AID PROJECT RS-0393 (105)				