

SUMMARY OF QUANTITIES			
PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
42001300	PROTECTIVE COAT	SQ YD	42668
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	4424
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	260
44000600	SIDEWALK REMOVAL	SQ FT	3948
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	892
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1
50800105	REINFORCEMENT BARS	POUND	97910
51500100	NAME PLATES	EACH	2
54001001	BOX CULVERT END SECTIONS, CULVERT NO. 1	EACH	2
54001002	BOX CULVERT END SECTIONS, CULVERT NO. 2	EACH	2
54001003	BOX CULVERT END SECTIONS, CULVERT NO. 3	EACH	2
54003000	CONCRETE BOX CULVERTS	CU YD	580.7
54010403	PRECAST CONCRETE BOX CULVERTS 4' X 3'	FOOT	98
54010404	PRECAST CONCRETE BOX CULVERTS 4' X 4'	FOOT	88
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	17
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	11
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"	EACH	4
54213687	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 42"	EACH	2
54260311	TRAVERSABLE PIPE GRATE	FOOT	62
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	1
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	6
60500080	REMOVING INLETS	EACH	4
61133100	FIELD TILE JUNCTION VAULTS, 2' DIA.	EACH	5
61133200	FIELD TILE JUNCTION VAULTS, 3' DIA.	EACH	5
61133300	FIELD TILE JUNCTION VAULTS, 4' DIA.	EACH	5
61133400	FIELD TILE JUNCTION VAULTS, 5' DIA.	EACH	5
61139900	STORM SEWERS (SPECIAL), 6"	FOOT	300
61140000	STORM SEWERS (SPECIAL), 8"	FOOT	300
61140100	STORM SEWERS (SPECIAL), 10"	FOOT	300
61140200	STORM SEWERS (SPECIAL), 12"	FOOT	300
61140400	STORM SEWERS (SPECIAL), 15"	FOOT	300
61140600	STORM SEWERS (SPECIAL), 18"	FOOT	300
61140900	STORM SEWERS (SPECIAL), 24"	FOOT	300