

SEEDING SCHEDULE (2 OF 2)						25000100	25000200	25100115	28000250	25000400	25000500	25000600
LOCATION	PLAN AREA	PLAN AREA	PLAN AREA X SLOPE FACTOR (1.03)	PLAN AREA X SLOPE FACTOR (1.06)	TOTAL AREA	SEEDING, CLASS 1	SEEDING, CLASS 2	MULCH, METHOD 2	TEMPORARY EROSION CONTROL SEEDING	FERTILIZER		
										NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT
STATION TO STATION	FORESLOPES (1:4)	BACKSLOPES (1:3)	FORESLOPES (1:4)	BACKSLOPES (1:3)					100 LBS/ACRE X 3 APPLICATIONS	90 LBS/ACRE	90 LBS/ACRE	90 LBS/ACRE
	SQ.FT.	SQ.FT.	SQ.FT.	SQ.FT.	SQ.FT.	ACRE	ACRE	ACRE	POUND	POUND	POUND	POUND
LEFT SIDE												
STA. 2+92.00 LT TO STA. 4+29.00 LT	1204.00	1489.00	1240.12	1578.34	2818.46		0.06	0.26	19.41	5.82	5.82	5.82
STA. 4+70.00 LT TO STA. 24+00.00 LT	21180.00	24227.00	21815.40	25680.62	47496.02		1.09	4.36	327.11	98.13	98.13	98.13
STA. 24+00.00 LT TO STA. 25+12.00 LT	937.00	2388.00	965.11	2531.28	3496.39	0.06	0.02	0.32	24.08	7.22	7.22	7.22
STA. 25+26.00 LT TO STA. 25+86.00 LT	541.00	1160.00	557.23	1229.60	1786.83	0.03	0.01	0.16	12.31	3.69	3.69	3.69
STA. 26+24.00 LT TO STA. 26+42.00 LT	135.00	337.00	139.05	357.22	496.27	0.01	0.00	0.05	3.42	1.03	1.03	1.03
STA. 26+42.00 LT TO STA. 28+77.00 LT	2051.00	3516.00	2112.53	3726.96	5839.49		0.13	0.54	40.22	12.07	12.07	12.07
STA. 29+23.00 LT TO STA. 38+99.00 LT	12862.00	16224.00	13247.86	17197.44	30445.30		0.70	2.80	209.68	62.90	62.90	62.90
STA. 38+99.00 LT TO STA. 40+41.00 LT	291.00	316.00	299.73	334.96	634.69	0.01	0.01	0.06	4.37	1.31	1.31	1.31
STA. 40+79.00 LT TO STA. 45+82.00 LT	3791.00	8298.00	3904.73	8795.88	12700.61		0.29	1.17	87.47	26.24	26.24	26.24
STA. 46+18.00 LT TO STA. 56+00.00 LT	14962.00	15707.00	15410.86	16649.42	32060.28		0.74	2.94	220.80	66.24	66.24	66.24
STA. 56+00.00 LT TO STA. 57+43.00 LT	1198.00	1832.00	1233.94	1941.92	3175.86	0.04	0.03	0.29	21.87	6.56	6.56	6.56
STA. 57+60.00 LT TO STA. 70+31.00 LT	12365.00	15518.00	12735.95	16449.08	29185.03		0.67	2.68	201.00	60.30	60.30	60.30
STA. 70+31.00 LT TO STA. 70+37.00 LT	489.00	903.00	503.67	957.18	1480.85		0.03	0.13	10.06	3.02	3.02	3.02
STA. 70+86.00 LT TO STA. 83+70.00 LT	41823.00	26770.00	43077.69	28376.20	71453.89		1.64	6.56	492.11	147.63	147.63	147.63
STA. 83+70.00 LT TO STA. 85+46.00 LT	1221.00	3276.00	1257.63	3472.56	4730.19	0.08	0.03	0.43	32.58	9.77	9.77	9.77
STA. 85+82.00 LT TO STA. 86+86.00 LT	1740.00	1482.00	1792.20	1570.92	3363.12	0.04	0.04	0.31	23.16	6.95	6.95	6.95
STA. 86+86.00 LT TO STA. 91+26.00 LT	7488.00	5457.00	7712.64	5784.42	13497.06		0.31	1.24	92.95	27.89	27.89	27.89
STA. 91+72.00 LT TO STA. 96+69.00 LT	4493.00	6780.00	4627.79	7186.80	11814.59		0.27	1.08	81.37	24.41	24.41	24.41
STA. 96+69.00 LT TO STA. 97+17.00 LT	429.00	567.00	441.87	601.02	1042.89	0.01	0.01	0.10	7.18	2.15	2.15	2.15
STA. 97+37.00 LT TO STA. 98+23.00 LT	1040.00	2920.00	1071.20	3095.20	4166.40	0.07	0.02	0.38	28.69	8.61	8.61	8.61
STA. 99+23.00 LT TO STA. 100+56.00 LT	1307.00	2197.00	1346.21	2328.82	3675.03		0.08	0.34	25.31	7.59	7.59	7.59
STA. 100+96.00 LT TO STA. 107+50.00 LT	8307.00	10709.00	8556.21	11351.54	19907.75		0.46	1.83	137.11	41.13	41.13	41.13
STA. 108+10.00 LT TO STA. 109+58.00 LT	3081.00	1415.00	3173.43	1499.90	4673.33		0.11	0.43	32.19	9.66	9.66	9.66
STA. 109+92.00 LT TO STA. 116+70.00 LT	7040.00	10980.00	7251.20	11638.80	18890.00		0.43	1.73	130.10	39.03	39.03	39.03
STA. 116+84.00 LT TO STA. 122+61.00 LT	13814.00	8713.00	14228.42	9235.78	23464.20		0.54	2.15	161.60	48.48	48.48	48.48
STA. 123+02.00 LT TO STA. 135+63.00 LT	14543.00	18118.00	14979.29	19205.08	34184.37		0.78	3.14	235.43	70.63	70.63	70.63
STA. 138+69.00 LT TO STA. 139+39.00 LT	538.00	813.00	554.14	861.78	1415.92		0.03	0.13	9.75	2.93	2.93	2.93
STA. 139+39.00 LT TO STA. 141+22.00 LT	990.00	3208.00	1019.70	3400.48	4420.18	0.08	0.02	0.41	30.44	9.13	9.13	9.13
STA. 141+46.00 LT TO STA. 142+09.00 LT	176.00	158.00	181.28	167.48	348.76	0.00	0.00	0.03	2.40	0.72	0.72	0.72
STA. 142+09.00 LT TO STA. 149+43.00 LT	7501.00	10863.00	7726.03	11514.78	19240.81		0.44	1.77	132.51	39.75	39.75	39.75
STA. 149+78.00 LT TO STA. 160+83.00 LT	15829.00	14573.00	16303.87	15447.38	31751.25		0.73	2.92	218.67	65.60	65.60	65.60
STA. 161+19.00 LT TO STA. 175+28.00 LT	14241.00	16025.00	14668.23	16986.50	31654.73		0.73	2.91	218.01	65.40	65.40	65.40
STA. 175+78.00 LT TO STA. 181+30.00 LT	6973.00	8615.00	7182.19	9131.90	16314.09		0.37	1.50	112.36	33.71	33.71	33.71
TOTAL LEFT SIDE ONLY						0.43	10.86	45.14	3385.71	1015.71	1015.71	1015.71
TOTAL LEFT & RIGHT SIDE						0.75	23.46	96.88	7265.94	2179.78	2179.78	2179.78

TEMPORARY DITCH CHECK SCHEDULE (1 OF 9)		28000305
LOCATION	TEMPORARY DITCH CHECKS	
STATION	FOOT	
RIGHT SIDE		
STA. 3+00.00 RT	14	
STA. 4+31.00 RT	14	
STA. 6+32.00 RT	14	
STA. 7+50.00 RT	14	
STA. 12+30.00 RT	14	
STA. 13+70.00 RT	14	
STA. 14+00.00 RT	14	
STA. 14+25.00 RT	14	
STA. 14+50.00 RT	14	
STA. 15+50.00 RT	14	
STA. 15+71.00 RT	14	
STA. 15+92.00 RT	14	
STA. 16+13.00 RT	14	
STA. 16+33.00 RT	14	
STA. 16+54.00 RT	14	
STA. 16+75.00 RT	14	
STA. 16+95.00 RT	14	
STA. 17+52.00 RT	14	
STA. 17+98.00 RT	14	
STA. 20+02.00 RT	14	
STA. 20+35.00 RT	14	
STA. 20+68.00 RT	14	
STA. 21+01.00 RT	14	
STA. 21+27.00 RT	14	
STA. 22+52.00 RT	14	
STA. 22+78.00 RT	14	
STA. 23+04.00 RT	14	
STA. 23+35.00 RT	14	
STA. 23+66.00 RT	14	
STA. 23+99.00 RT	14	
STA. 24+32.00 RT	14	
STA. 24+65.00 RT	14	
STA. 24+98.00 RT	14	
STA. 25+58.00 RT	14	
STA. 26+18.00 RT	14	
STA. 26+78.00 RT	14	
STA. 28+78.00 RT	14	
STA. 30+78.00 RT	14	
STA. 31+53.00 RT	14	
STA. 32+28.00 RT	14	
STA. 32+52.00 RT	14	
STA. 32+77.00 RT	14	
STA. 33+27.00 RT	14	
STA. 36+99.00 RT	14	
STA. 37+52.00 RT	14	
STA. 37+97.00 RT	14	
STA. 38+18.00 RT	14	
STA. 38+40.00 RT	14	
STA. 38+61.00 RT	14	
STA. 39+43.00 RT	14	
STA. 41+00.00 RT	14	
STA. 41+39.00 RT	14	
STA. 41+78.00 RT	14	
STA. 42+17.00 RT	14	
STA. 42+56.00 RT	14	
STA. 42+95.00 RT	14	
STA. 43+34.00 RT	14	
STA. 43+73.00 RT	14	
STA. 44+12.00 RT	14	
STA. 44+40.00 RT	14	
STA. 44+68.00 RT	14	
STA. 44+98.00 RT	14	
STA. 45+24.00 RT	14	
STA. 45+57.00 RT	14	
STA. 45+90.00 RT	14	
STA. 46+22.00 RT	14	
STA. 46+50.00 RT	14	
STA. 46+78.00 RT	14	
STA. 47+05.00 RT	14	
STA. 47+39.00 RT	14	
STA. 47+80.00 RT	14	
STA. 49+12.00 RT	14	
SUBTOTAL 1	1008	

TEMPORARY DITCH CHECK SCHEDULE (2 OF 9)		28000305
LOCATION	TEMPORARY DITCH CHECKS	
STATION	FOOT	
RIGHT SIDE		
STA. 49+55.00 RT	14	
STA. 49+97.00 RT	14	
STA. 50+41.00 RT	14	
STA. 50+84.00 RT	14	
STA. 51+27.00 RT	14	
STA. 52+93.00 RT	14	
STA. 53+41.00 RT	14	
STA. 53+89.00 RT	14	
STA. 54+37.00 RT	14	
STA. 54+85.00 RT	14	
STA. 55+27.00 RT	14	
STA. 55+69.00 RT	14	
STA. 56+11.00 RT	14	
STA. 56+53.00 RT	14	
STA. 57+36.00 RT	14	
STA. 59+07.00 RT	14	
STA. 61+07.00 RT	14	
STA. 63+50.00 RT	14	
STA. 64+00.00 RT	14	
STA. 64+71.00 RT	14	
STA. 65+42.00 RT	14	
STA. 66+36.00 RT	14	
STA. 68+36.00 RT	14	
STA. 68+90.00 RT	14	
STA. 69+44.00 RT	14	
STA. 69+98.00 RT	14	
STA. 71+00.00 RT	14	
STA. 71+33.00 RT	14	
STA. 71+66.00 RT	14	
STA. 72+03.00 RT	14	
STA. 72+40.00 RT	14	
STA. 73+48.00 RT	14	
STA. 74+10.00 RT	14	
STA. 74+73.00 RT	14	
STA. 74+97.00 RT	14	
STA. 75+20.00 RT	14	
STA. 75+44.00 RT	14	
STA. 75+67.00 RT	14	
STA. 75+91.00 RT	14	
STA. 76+15.00 RT	14	
STA. 76+38.00 RT	14	
STA. 76+95.00 RT	14	
STA. 77+22.00 RT	14	
STA. 77+50.00 RT	14	
STA. 77+78.00 RT	14	
STA. 78+07.00 RT	14	
STA. 78+29.00 RT	14	
STA. 78+51.00 RT	14	
STA. 78+72.00 RT	14	
STA. 78+94.00 RT	14	
STA. 79+16.00 RT	14	
STA. 79+38.00 RT	14	
STA. 79+60.00 RT	14	
STA. 79+82.00 RT	14	
STA. 80+04.00 RT	14	
STA. 80+43.00 RT	14	
STA. 80+82.00 RT	14	
STA. 81+21.00 RT	14	
STA. 81+60.00 RT	14	
STA. 81+99.00 RT	14	
STA. 83+99.00 RT	14	
STA. 85+95.00 RT	14	
STA. 86+23.00 RT	14	
STA. 86+52.00 RT	14	
STA. 86+81.00 RT	14	
STA. 87+01.00 RT	14	
STA. 87+38.00 RT		