

SUBBASE GRANULAR MATERIAL, TYPE B						31101100
LOCATION	LENGTH	WIDTH	DEPTH	VOLUME	VOLUME	
STATION TO STATION	FOOT	FOOT	FOOT	CU. FT.	CU. YD.	
<b>UNDER THE ROADWAY</b>						
STA. 14+00.00 TO STA. 15+00.00	100	24	2.00	4800	177.78	
STA. 66+00.00 TO STA. 70+00.00	400	24	2.25	21600	800.00	
CONTINGENT QTY UNDER THE ROADWAY	1000	24	2.00	48000	1777.78	
<b>TOTAL</b>					<b>2755.56</b>	

AGGREGATE BASE COURSE, TYPE A					35100700	35101100	35101350	
LOCATION	ALIGNMENT	LENGTH	WIDTH	AREA	8"	12"	15"	
STATION TO STATION		FOOT	FOOT	SQ. FT.	SQ. YD.	SQ. YD.	SQ. YD.	
STA. 3+15.00 TO STA. 56+00.00	COUNTY HIGHWAY #4	5285.00	24	126840.00	14093.33			
STA. 56+00.00 TO STA. 66+00.00	COUNTY HIGHWAY #4	1000.00	24	24000.00		2666.67		
STA. 66+00.00 TO STA. 107+50.00	COUNTY HIGHWAY #4	4150.00	24	99600.00	11066.67			
STA. 108+10.00 TO STA. 143+00.00	COUNTY HIGHWAY #4	3490.00	24	83760.00	9306.67			
STA. 143+00.00 TO STA. 147+00.00	COUNTY HIGHWAY #4	400.00	24	9600.00		1066.67		
STA. 147+00.00 TO STA. 165+00.00	COUNTY HIGHWAY #4	1800.00	24	43200.00	4800.00			
STA. 165+00.00 TO STA. 169+00.00	COUNTY HIGHWAY #4	400.00	24	9600.00		1066.67		
STA. 169+00.00 TO STA. 178+30.00	COUNTY HIGHWAY #4	930.00	24	22320.00	2480.00			
STA. 178+30.00 TO STA. 181+30.00	COUNTY HIGHWAY #4	300.00	22	6600.00			733.33	
STA. 1602+30.00 TO STA. 1604+88.00	TR 1600 E	258.00	VARIES	7224.59	802.73			
STA. 1605+12.00 TO STA. 1607+00.00	TR 1600 E	188.00	VARIES	5587.78	620.86			
STA. 1704+21.74 TO STA. 1704+87.90	TR 1700 E	66.16	VARIES	2671.37	296.82			
STA. 1705+11.90 TO STA. 1705+78.12	TR 1700 E	66.22	VARIES	2678.94	297.66			
STA. 1802+40.00 TO STA. 1804+88.00	COUNTY HIGHWAY #15	248.00	VARIES	7024.48		780.50		
STA. 1805+12.00 TO STA. 1805+79.95	TR 1800 E	67.95	VARIES	2719.55	302.17			
<b>TOTAL</b>					<b>453428.71</b>	<b>44066.91</b>	<b>5580.50</b>	<b>733.33</b>

ROADWAY PAVEMENT SCHEDULE						40600115	40600100	40600982	40603080	40603310	42000201	42001300	X4020800	
LOCATION	ALIGNMENT	LENGTH	WIDTH	AREA		POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	BITUMINOUS MATERIALS (PRIME COAT)	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	PORTLAND CEMENT CONCRETE PAVEMENT 7" (JOINTED)	PROTECTIVE COAT	AGGREGATE SURFACE COURSE, TYPE B 12"	
				SQ. FT.	SQ. YD.	VOLUME GALLON	VOLUME GALLON	AREA SQ. YD.	WEIGHT TON	WEIGHT TON	AREA SQ. YD.	AREA SQ. YD.	AREA SQ. YD.	
STA. 2+58.00 TO STA. 2+95.20	COUNTY HIGHWAY #4	37.20	22	818.40	90.93	11.82		90.93		10.18				
STA. 2+95.20 TO STA. 3+15.00	COUNTY HIGHWAY #4	19.80	22	435.60	48.40	6.29				9.22				
STA. 3+15.00 TO STA. 107+50.00	COUNTY HIGHWAY #4	10435.00	22	229570.00	25507.78						25507.78	25507.78		
STA. 107+50.00 TO STA. 108+10.00	COUNTY HIGHWAY #4	60.00	22	1320.00	146.67	7.33				12.32				
STA. 108+10.00 TO STA. 178+30.00	COUNTY HIGHWAY #4	7020.00	22	154440.00	17160.00						17160.00	17160.00		
STA. 1602+30.00 TO STA. 1604+89.00	TR 1600 E	259.00	VARIES	6785.54	753.95	37.70	376.97	147.77	84.44					
STA. 1605+11.00 TO STA. 1607+00.00	TR 1600 E	189.00	VARIES	5289.21	587.69	29.38	293.85	115.19	65.82					
STA. 1703+45.00 TO STA. 1704+21.74	TR 1700 E	76.74	VARIES	1770.05	196.67								196.67	
STA. 1704+21.74 TO STA. 1704+88.90	TR 1700 E	67.16	VARIES	2603.14	289.24	14.46	144.62	56.69	32.39					
STA. 1705+10.90 TO STA. 1705+78.12	TR 1700 E	67.22	VARIES	2611.42	290.16	14.51	145.08	56.87	32.50					
STA. 1705+78.12 TO STA. 1706+50.00	TR 1700 E	71.88	VARIES	1587.64	176.40								176.40	
STA. 1802+40.00 TO STA. 1804+89.00	TR 1800 E	249.00	VARIES	6620.32	735.59	73.56	367.80	185.37	82.39					
STA. 1805+11.00 TO STA. 1805+79.95	TR 1800 E	68.95	VARIES	2645.94	293.99	29.40	147.00	57.62	32.93					
STA. 1805+79.95 TO STA. 1806+29.95	TR 1800 E	50.00	VARIES	1091.51	121.28								121.28	
<b>TOTAL</b>					<b>417588.77</b>	<b>46398.75</b>	<b>224.46</b>	<b>1475.31</b>	<b>90.93</b>	<b>619.51</b>	<b>362.19</b>	<b>42667.78</b>	<b>42667.78</b>	<b>494.36</b>

CAST IN PLACE BOX CULVERT SCHEDULE					50800105	51500100	54003000
LOCATION	SIZE	REINFORCEMENT BARS	NAME PLATES	CONCRETE BOX CULVERTS			
STATION	FOOT	WEIGHT POUND	UNIT EACH	VOLUME CU. YD.			
STA. 16+98.25	TRIPLE 11' X 10'	76330.0	1.0	429.4			
STA. 47+59.00	DOUBLE 9' X 8'	21580.0	1.0	151.3			
<b>TOTAL</b>					<b>97910.0</b>	<b>2.0</b>	<b>580.7</b>

PRECAST BOX CULVERT SCHEDULE								54001001	54001002	54001003	54010403	54010404	54260311
LOCATION	ALIGNMENT	BOX CULVERT END SECTIONS, CULVERT NO. 1	BOX CULVERT END SECTIONS, CULVERT NO. 2	BOX CULVERT END SECTIONS, CULVERT NO. 3	PRECAST CONCRETE BOX CULVERTS 4' X 3'	PRECAST CONCRETE BOX CULVERTS 4' X 4'	TRAVERSABLE PIPE GRATE						
STATION		UNIT EACH	UNIT EACH	UNIT EACH	LENGTH FOOT	LENGTH FOOT	LENGTH FOOT						
STA. 76+68.00	COUNTY HIGHWAY #4	2.0											
STA. 145+12.89	COUNTY HIGHWAY #4		2.0		62.0	88.0							
STA. 151+70.00	COUNTY HIGHWAY #4			2.0	36.0		62.0						
<b>TOTAL</b>		<b>2.0</b>	<b>2.0</b>	<b>2.0</b>	<b>98.0</b>	<b>88.0</b>	<b>62.0</b>						

PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH					42400100
LOCATION	LT/RT	LENGTH	WIDTH	AREA	
STATION TO STATION		FOOT	FOOT	SQ. FT.	
STA. 2+83.11 TO STA. 3+65.80	RT	82.69	5.00	413.45	
STA. 3+76.19 TO STA. 5+63.29	RT	187.10	5.00	935.50	
STA. 4+44.53 WALKWAY	RT	4.00	5.00	20.00	
STA. 5+73.71 TO STA. 7+79.80	RT	206.09	5.00	1030.45	
STA. 6+23.22 WALKWAY	RT	4.00	5.00	20.00	
STA. 7+32.56 WALKWAY	RT	4.00	5.00	20.00	
STA. 7+90.20 TO STA. 9+12.80	RT	122.60	5.00	613.00	
STA. 9+23.20 TO STA. 10+46.80	RT	123.60	5.00	618.00	
STA. 9+99.63 WALKWAY	RT	4.00	5.00	20.00	
STA. 10+57.20 TO STA. 12+00.00	RT	142.80	5.00	714.00	
STA. 11+94.37 WALKWAY	RT	4.00	5.00	20.00	
<b>TOTAL</b>					<b>4424.40</b>

PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH					42400300
LOCATION	LT/RT	LENGTH	WIDTH	AREA	
STATION TO STATION		FOOT	FOOT	SQ. FT.	
STA. 3+65.80 TO STA. 3+76.19	RT	10.39	5.00	51.95	
STA. 5+63.29 TO STA. 5+73.71	RT	10.42	5.00	52.10	
STA. 7+79.80 TO STA. 7+90.20	RT	10.40	5.00	52.00	
STA. 9+12.80 TO STA. 9+23.20	RT	10.40	5.00	52.00	
STA. 10+46.80 TO STA. 10+57.20	RT	10.40	5.00	52.00	
<b>TOTAL</b>					<b>260.05</b>

SIDEWALK REMOVAL			44000600
LOCATION	LT/RT	AREA	
STATION TO STATION		SQ. FT.	
STA. 2+74.34 TO STA. 12+61.25	RT	3947.64	
<b>TOTAL</b>			<b>3947.64</b>

REMOVAL OF EXISTING STRUCTURES NO. 1		50100300
LOCATION	UNITS	
STATION	EACH	
DOUBLE 10' X 8' BOX CULVERT STA. 16+98.25	1.0	
<b>TOTAL</b>		<b>1.0</b>

REMOVAL OF EXISTING STRUCTURES NO. 2		50100400
LOCATION	UNITS	
STATION	EACH	
SINGLE 12' X 9' BOX CULVERT STA. 47+59.00	1.0	
<b>TOTAL</b>		<b>1.0</b>