



Notes:
 Anchor bolts shall be installed only if sufficient reinforcement is not available for re-use in the location designated for the anchor bolt.
 Existing reinforcement shall be cleaned and incorporated, unless new reinforcement bars are designated in the plans.
 The proposed headwall and toe wall shall be constructed and paid as Concrete Box Culverts.
 The existing concrete parapets shall be salvaged and transported to the County highway office by the Contractor.
 CLSM shall be constructed to stabilize the box culvert before concrete removal and repairs begin.

FILE NAME # 100001-eh-culvert.dgn	USER NAME #	DESIGNED - L.A.P.	REVISED -	STATE OF ILLINOIS STARK COUNTY HIGHWAY DEPARTMENT	CULVERT DETAILS STRUCTURE NO. 088-3203	C.H.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
HAMPTON, LENZINI AND RENWICK, INC. 3035 STEVENSON DRIVE, SUITE 201 SPRINGFIELD, ILLINOIS 62765	FLOT SCALE #	CHECKED - S.W.M.	REVISED -			3	10-00163-00-BR	STARK	29	8	
ELR ILLINOIS PROFESSIONAL DESIGN FIRMS LLP / PC CORP. 164300930	FLOT DATE # 4/8/2013	DRAWN - D.A.B.	REVISED -			SOUTH VALLEY ROAD CONTRACT NO. 89621					
		CHECKED - S.W.M.	REVISED -			ILLINOIS FED. AID PROJECT					