

SUMMARY OF QUANTITIES						
				CONSTRUCTION TYPE CODE		
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0005 ROADWAY	0011 STRUCTURE	0042 TRAINEES
20100500	TREE REMOVAL, ACRES	ACRE	0.1	0.1		
* 20200100	EARTH EXCAVATION	CU YD	2840	2840		
* 20200500	EARTH EXCAVATION (WIDENING)	CU YD	43	43		
20800150	TRENCH BACKFILL	CU YD	72	72		
25000200	SEEDING, CLASS 2	ACRE	0.7	0.7		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	63	63		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	63	63		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	63	63		
25000700	AGRICULTURAL GROUND LIMESTONE	TON	1.4	1.4		
25100115	MULCH, METHOD 2	ACRE	0.7	0.7		
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	500	500		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	150	150		
* 28000315	AGGREGATE DITCH CHECKS	TON	25	25		
28000400	PERIMETER EROSION BARRIER	FOOT	175	175		
28000500	INLET AND PIPE PROTECTION	EACH	3	3		
* 28100207	STONE RIPRAP, CLASS A4	TON	973		973	
* 28100807	STONE DUMPED RIPRAP, CLASS A4	TON	65	65		
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	226	226		
35100100	AGGREGATE BASE COURSE, TYPE A	TON	23	23		
35650300	BASE COURSE WIDENING 8"	SQ YD	288	288		
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	171	171		
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	50	50		

* SPECIAL PROVISION

FILE NAME =	USER NAME = bgj	DESIGNED - SEB	REVISED - SEB - 1/16/13	ADAMS COUNTY HIGHWAY DEPARTMENT	FAS 1598 (CH 27 /CANNONBALL ROAD) SUMMARY OF QUANTITIES		F.A.S. RTE.	SECTION	COUNTY	TOTAL SHEET SHEETS: NO.
D:\11files\110015\05 Plans\Current\SHL\Sunary_11015.dgn		DRAWN - EBB	REVISED -				1598	11-00218-00-BR	ADAMS	53 3
	PLOT SCALE = 20.0000' / in.	CHECKED - SRW	REVISED -		CONTRACT NO. 939					
	PLOT DATE = 1/30/2013	DATE - 6-21-12	REVISED -		SCALE: NONE	SHEET NO. 1 OF 4 SHEETS	STA.	TO STA.	ILLINOIS FED. AID PROJECT	