


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				ROADWAY	BRIDGE
				0004 URBAN	0011 084-6019
28000400	PERIMETER EROSION BARRIER	FOOT	890	890	
28000500	INLET AND PIPE PROTECTION	EACH	3	3	
28100207	STONE RIPRAP, CLASS A4	TON	2130	2130	
28200200	FILTER FABRIC	SQ YD	3030	3030	
31100100	SUBBASE GRANULAR MATERIAL, TYPE A	TON	5145	5145	
35501326	HOT-MIX ASPHALT BASE COURSE, 10 1/2"	SQ YD	4467	4467	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	74	74	
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	376	376	
• 40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	88	88	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	117	117	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	224	224	
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	5527	5527	
42400800	DETECTABLE WARNINGS	SQ FT	38	38	
• 44000100	PAVEMENT REMOVAL	SQ YD	3450	3450	

• SEE SPECIAL PROVISIONS

FILE NAME = #FILE#	USER NAME = #USER#	DESIGNED - DRAWN -	REVISED - REVISED -	 Allen Henderson & Associates, Inc. Civil and Structural Engineers Springfield, IL. 62703 Phone: (217)544-8033 IL Design Firm No. 184-001907	SUMMARY OF QUANTITIES			F.A.U. RTE. 8006	SECTION 10-00470-00-BR	COUNTY SANGAMON	TOTAL SHEETS 90	SHEET NO. 4
PLOT SCALE = #SCALE#	CHECKED -	REVISED -	REVISED -		SCALE: NONE	SHEET NO. 2 OF 9 SHEETS	STA.	TO STA.	CONTRACT NO. 93600			
PLOT DATE = #DATE#	DATE -	REVISED -	REVISED -		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							